Big Dutchman Creek Watershed Plan

Wdhec

Spring 2024















SCR






Table of Contents

Introduction pg. 06 The Nine Required Plan Elements The Watershed Planning Process

Watershed Overview pa. 12

Watershed Assets Streams & Impoundments Floodplains Riparian Buffers Soils

Typography Land Use Water Supplies Population Projections Local Interest

Watershed Analysis pg. 32 Water Quality Classification & Standards

Impairments & TMDLS & Watershed Plans E. Coli Description & Monitoring Data Total Nitrogen & Phosphorus Description Hydrologic Impacts

Pollutant Sources pg. 42

Summary of Impairments, Causes, Sources & Impacts Septic Systems in the Watershed Nonpoint Sources Within the Watershed Pollutant Loading Estimate

Load Reductions pg. 56 Watershed Plan Review

Descriptions pg. 60 of Management Measures

Summary Objective 1 Measures Objective 2 Measures Objective 3 Measures Pollutant Removal & Implementation Cost Est.



5

Climate Change pg. 78 Temperature Increases Higher Variability in Rainfall

Methods for Improving Climate Resiliency

Environmental pg. 86 **Justice (EJ)**

Watershed Demographics Environmental Justice Considerations



Acknowledgments City of Rock Hill

This project was funded wholly or in part by the US EPA under a capitalization grant for the Drinking Water State Revolving Fund through the South Carolina Department of Health and Environmental Control

City of Rock Hill David Dickson City Engineer III, Public Works City of Rock Hill P.O. Box 11706 Rock Hill, SC 29731-1706 (803) 329-7096





Financial & Technical Assistance pg. 92

Cost Estimate for Watershed Plan Funding Sources and Partners



Education & Outreach pg. 98

Overview Current Public Perceptions Ten Methods to Make it Fun & Creative **Outreach & Education Management Measures**



Implementation Timeline & Milestones pg. 108 Overview Milestone Timeframe



Evaluation Criteria pg. 114



Overview Digital Watershed Dashboard Evaluation Criteria




Monitoring pa. 118

Overview Sampling Points Sampling Parameters







Introduction

A watershed is an area of land that channels rainfall and occasionally snowmelt to streams and rivers. All land is part of a watershed, and watersheds do not follow jurisdictional boundaries.

Watersheds play a pivotal role in collecting, filtering, and supplying water to ecosystems and human communities, as shown in Figure 1. Watershed Plans serve as a roadmap to maintain and improve watershed health by providing voluntary recommendations to address known water quality impairments within the watershed. By promoting sustainable land and water management practices, this Watershed Plan seeks to ensure that both natural ecosystems and human communities can thrive and coexist harmoniously, safeguarding our vital water resources for future generations

One of the biggest benefits of creating a Watershed Plan is that it makes the watershed eligible for state and federal grants to address pollution problems in the watershed. One of those funding sources is the Section 319 Nonpoint Source Management Program. These are federal monies that are awarded by the South Carolina Department of Health and Environmental Control (DHEC) to support public education, technical training, and management measures to improve water quality.



Figure 1. Diagram of a watershed (University of Maryland)

The Nine Required Plan Elements

The Nine Required Elements are displayed below that must be included in a Watershed Plan are determined by the United States Environmental Protection Agency (EPA). In combination, these elements explain the community's concerns with the watershed, creates a strategy to address those concerns, and includes a plan to monitor progress.

- **A.** Identify causes of impairment and pollution sources
- **B.** Estimate load reductions expected from management measures
- **C.** Describe management measures to be implemented
- **D.** Estimate technical and financial assistance needed
- **E.** Include informational and educational components

- **F.** Create a schedule for implementation of management measures
- **G.** Describe the interim measurable milestones
- **H.** Determine criteria to measure success
- Create a monitoring plan



In the Big Dutchman Creek Watershed there are many organizations already active and engaged in local water quality issues. Leaders of those organizations were invited to participate as Key Partners on this Watershed Planning process. It would not have been possible to create this Watershed Plan without the assistance of the Key Partners. The Key Partners supported the project in the following ways:

- Creating goals and a schedule for the project;
- Sharing their concerns about the water quality of the watershed;
- Organizing the information into an outline for the document;
- Leading field visits to areas of concern within the watershed; and
- Sharing data that was needed to successfully complete the assessment.

In addition to the input from the Key Partners, input from the public was also sought. The Watershed Planning process was highlighted on a local radio show (Rick Lee, WEHI) and the public was invited to provide input via a digital survey. The information gained from the survey was used to identify key pollution issues, sources and to prioritize management measures.

Figure 2. Photo of completed stream restoration (McAdams)

The Key Partners included the following communities and organizations:

Catawba Nation Catawba River Keeper City of Rock Hill Keep York County Beautiful Rock Hill Clean and Green

SC Department of Health and Environmental Control (DHEC)

SC Rural Water Association WRHI FM 100.1

York County York Soil and Water Conservation District

> All the management measures presented in a Watershed Plan are strictly voluntary.

Thank you DHEC for your assistance and expertise in the development of this Watershed Plan.


Key Terms

The following key terms are used throughout this document and will be helpful for the reader to understand.

- **BMPs** are structural, vegetative or managerial practices used to treat, prevent or reduce water pollution.
- **Detention Basins** are structural BMPs that capture stormwater runoff to reduce flooding and remove pollutants before discharging it at a controlled rate until they are completely drained. Detention basins are designed to be dry between storm events and thus are also called "dry ponds."
- **E. coli** is the shorter name for the *Escherichia coli* bacteria. This bacteria is found in the fecal matter of humans and animals, and can cause illness.
- **Floodplains** are the low-lying areas that surround rivers and other waterbodies that naturally flood on a frequent basis.
- **Impoundments** are manmade or naturally occurring standing waterbodies, often produced by dams on streams or rivers.
- **Infiltration** is the process by which water moves from the surface into the ground. Infiltration is one of the most effective methods for improving water quality and reducing water quantity.
- **Impaired Waters** are waters listed on the 303(d) list because they do not currently meet State water quality standards after application of required controls for point and nonpoint source pollutants (DHEC, 2022).
- **Intermittent Streams** are streams that have flowing water during certain times of the year, when groundwater and/or precipitation provides water for stream flow.
- Perennial Streams are streams that have flowing water year-round during a typical year.
- **Pollutant Loading** is the measure of how much of a particular pollutant reaches a waterbody in a unit of time. For example, the pollutant load may be expressed as pounds of pollutant per day or as tons of pollutant per year.
- **Retention Basins** are structural BMPs that capture stormwater runoff to reduce flooding and remove pollutants before discharging it at a controlled rate. Retention basins are designed to permanently hold water between storm events and thus are also called "wet ponds."
- **Riparian Buffers** are areas adjacent to streams, lakes, and wetlands containing trees, shrubs, and other plants.
- **Runoff** is water from precipitation events that flows over surfaces such as the ground, rooftops, or pavement.
- Stormwater is any liquid precipitation, such as rain or snow.
- Total Nitrogen includes nitrite (NO₂), nitrate (NO₃), ammonia (NH₃), and organic nitrogen.
- Total Phosphorus includes both dissolved phosphorus and particulate forms.
- **Watersheds** are areas of land where all stormwater runoff flows to a common waterbody. Watersheds may be comprised of smaller "sub-watersheds."
- Wetlands are areas where the water table is usually at or near the surface or the land is covered by shallow water.



Figure 3. Gazebo overlooks the Big Dutchman Creek as it flows into the Catawba River (McAdams)



Watershed Overview

The Big Dutchman Creek Watershed has many assets that are important to the quality of life, economy, and environment of Rock Hill and the surrounding communities.

Watershed Assets

The Big Dutchman Creek Watershed is home to approximately 28,000 people, and most of the land is devoted to providing housing, parks, medical offices, and businesses to support its residents and visitors. The watershed also includes the York County airport and the Museum of York County, shown in Figure 1.2, has exhibits, a naturalist center, trails and a planetarium. Bike trails and parks, like those shown in Figure 1.3 and 1.4, enable people to enjoy the natural amenities of the area on foot or bicycle. This watershed is part of the Charlotte metropolitan area, and thus offers a wide variety of employment, academic, and entertainment opportunities to people who live here. The watershed's location relative to major cities is shown in Figure 1.1.

Key Watershed Facts






Figure 1.1 Watershed location




Figure 1.2 York County 101 Citizens Academy hosted at the Museum of York County (Museum of York County



Figure 1.3 Piedmont Medical Center trail (Carolina Thread Trail 2023)





Figure 1.4 Piedmont Medical Center trail (Carolina Thread Trail 2023)

Perennial and Intermittent Stream Miles

Streams & Impoundments

The Big Dutchman Creek Watershed contains approximately 57 miles of streams and 33.1 acres of impoundments. As water moves through the watershed, it collects to form waterways such as intermittent streams, perennial streams, and impoundments. Figure 1.5 shows an perennial stream within the watershed and Figure 1.6 shows an example of an intermittent stream. This flowing water can also pick up pollutants from the land and carry those pollutants into and through the watershed: Big Dutchman Creek and Little Dutchman Creek. These streams join in the eastern part of the watershed and eventually drain to the Catawba River.




Figure 1.5 A perennial stream in the Big Dutchman Creek Watershed (McAdams)



Figure 1.6 An intermittent stream (Army Corps of Engineers)

There are nearly three times more miles of intermittent streams than perennial streams in the watershed, as shown in Figure 1.7. Even though intermittent streams typically flow for only part of the year, they provide food and habitat for many types of animals. Some of the intermittent streams have been piped under areas of development in the locations where they appear disconnected on the adjacent map (Figure 1.8).

The impoundments shown on the map consist of lakes, ponds and wetlands. Those features are spread evenly throughout the watershed. Although impoundments can be helpful in controlling flooding, they can alter the natural flow regime of streams when they are placed "on-line," or directly in the stream channel. Online impoundments can cause sediment to build up in stream channels and degrade the habitat of aquatic animals.






Figure 1.8 Streams and impoundments in watershed

Floodplains

Floodplains are the low-lying areas that surround rivers and other waterbodies that naturally flood on a frequent basis, as shown in Figure 1.9. Floodplains are important to a healthy environment because they provide clean water and wildlife habitat. If left undisturbed, floodplains protect citizens from flooding by storing large volumes of stormwater and releasing it slowly over time. The Big Dutchman Creek floodplain becomes much wider where Big Dutchman Creek and Little Dutchman Creek join and remains wide until Big Dutchman Creek discharges into the Catawba River.

The Federal Emergency Management Agency (FEMA) categorizes floodplains to reflect the frequency of flooding. FEMA Flood Zone categories are summarized in Figure 1.10. Floodplains within the watershed are shown in Figure 1.11.




Figure 1.9 Floodplain storing water after a large storm event (City of Austin, Texas)

Flood Zone	Risk Level
100-Year	High
500-Year	Moderate to Low

Figure 1.10 Table summarizing FEMA Flood Zones (FEMA 2020)




Figure 1.11 Floodplains in watershed

Description

Areas with a 1% chance of flooding in any given year and a 26% chance of flooding over the life of a 30year mortgage.

Areas with a 0.2% chance of flooding in any given year

Riparian Buffers

A riparian buffer is a protected area adjacent to a stream, lake, or wetland containing trees, shrubs, and other plants. Riparian buffers, particularly forested buffers adjacent to headwater streams, deliver tremendous benefits, as summarized in Figure 1.12. In a riparian buffer, stormwater and water in the stream interact with soil, plant roots, insects, and other living things that together remove pollutants such as nutrients and harmful bacteria (Klapproth 2009). Fortunately, all the jurisdictions within this watershed require some protection of riparian buffers. Jurisdictional protections are summarized in Figure 1.13 and shown in Figure 1.14. The benefits of riparian buffers are explained in the figures below.




Figure 1.12 Diagram of riparian buffer benefits (Highland)

Rock Hill requires riparian buffer protection in Section 8.4 of the Rock Hill Zoning Ordinance. York County covers riparian buffer protection on pages 343-340 of the York County, Chapter 155 Code of Ordinances.

Jurisdiction	Waterbody Type	Width (Feet)	Notes
Rock Hill	Catawba River	125	 100' undisturbed, 25' transition zone Will span the entire floodplain instead if it is wider than 125'
Rock Hill	Perennial Stream	75	 50' undisturbed, 25' transition zone Will span the entire floodplain if it is wider than 75'
Rock Hill	Intermittent Streams, Wetlands & Ponds	50	• 40' undisturbed, 10' transition zone
York Co.	Catawba River	100	
York Co.	Perennial Stream	50	

Figure 1.13 Table summarizing riparian buffer width requirements




Figure 1.14 Stream buffer limits in watershed

protection of buffer function. Examples of these uses include:

- Maintaining existing structures;
- Planting additional trees, shrubs, and native plants;
- Removing large debris;
- Stabilizing the shoreline (with approval)
- Installing water-dependent structures such as docks (with approval); and
- approval)

Rock Hill and York County allow some limited activities to balance access to water resources and

• Installing paths or stairs to water-dependent structures (with limitations on width/area and

0

Total

Freshwater Emergent Wetland

Forested/Shrub Wetland

Wetlands

The USGS defines wetlands as transitional areas where water is frequently present either just above or below the land surface. Emergent wetlands are dominated by perennial plants that are water-loving and have vegetation present for most of the growing season in most years (Figure 1.15). Forest/shrub wetlands have at least 30% areal coverage of trees and shrubs, and vegetation is present all year but will lose its leaves during the winter (Figure 1.16).

The data to support this watershed assessment was gathered from the <u>Wetlands Mapper</u>, which is maintained by the National Wetlands Inventory Program (under the U.S. Fish and Wildlife Service). Wetlands comprise a total of approximately 66 acres, or 5.7% of the total watershed land area, as shown in Figure 1.17 and 1.18.

Although this is a small percentage of the watershed's overall land area, their contribution is significant because they:


- Provide a home and a food source to a diverse array of microbes, plants, insects, amphibians, reptiles, birds, fish and • mammals;
- Prevent flooding by storing stormwater during large rain events; and •
- Moderate both local and global temperatures.



Figure 1.15 An emergent wetland (US Department of Agriculture)




Figure 1.16 A forested wetland (NC Wetlands)





Wetlands in Watershed (acres)



Soils

The USDA groups soils into four hydrologic soil groups (HSGs). HSG A soils are sandier and tend to soak rainwater into the ground rather than producing stormwater runoff. HSG D soils, on the other hand, have more clay particles and do not soak up as much stormwater, and thus produce a high amount of stormwater. A summary of HSGs is provided in Figure 1.19. Highly urban areas are sometimes not classified by the USDA, but often act like HSG D soils due to the soil disturbance and compaction that occur during the construction process. Soils in the watershed are 47% urban unclassified, which is assumed as HSG D. Another 23% of the soils are classified as D, as shown in Figures 1.20 and 1.21. Therefore, a total of 71% of soils in the watershed have high runoff potential and low infiltration rates, resulting in large volumes and high rates of stormwater runoff. This can compromise the functioning of septic systems and make it difficult to implement stormwater BMPs that rely on infiltration to function, effectively such as permeable pavement.

HSG	Runoff Implications	Soil Properties
А	Low runoff, high infiltration	Less than 10% clay & more than 90% sand or gravel
В	Moderately low runoff, moderately high infiltration	10-20% clay & 50-90% sand
С	Moderately high runoff, moderately low infiltration	20-40% clay & less than 50% sand
D	High runoff, low infiltration	More than 40% clay & less than 50% sand
D Assumed	Assumed high runoff, low infiltration	Highly disturbed & compacted from development

Figure 1.19 Table showing properties of Hydrologic Soil Groups






Figure 1.20 Chart showing soils in watershed




Figure 1.21 Soils in watershed

Topography

Topography plays a crucial role in a watershed because water always flows downhill. The perimeter of a watershed typically contains the highest elevation in the watershed; in fact, a watershed boundary is a ridge that separates one watershed from another. Topographic maps use elevation contour lines or color scales to illustrate the shape of the Earth's surface and usually contain additional geographic features such as roads, rivers, streams, lakes, and jurisdictional boundaries.

In the Big Dutchman Creek Watershed, elevations range between 492 feet to 724 feet above sea level. Figure 1.22 shows that the highest elevations are around the watershed boundary and the lowest are near the watershed outlet to the Catawba River. Overall, the terrain in the watershed is rolling hills. Where Big Dutchman Creek and Little Dutchman Creek join, the floodplain becomes much wider and remains wide until Big Dutchman Creek discharges into the Catawba River.




Figure 1.22 Topography in watershed

Land Use

The amount of runoff and types of pollutants generated in a watershed often correspond to land use. Approximately 90% of the watershed is developed, with the remaining 10% forested or undeveloped. Nearly 60% of the land in the Big Dutchman Creek Watershed is comprised of residential development, most of which is single-family residences. These features can be seen in the aerial image of the watershed below (Figure 1.23). Some of the notable non-residential land uses in the watershed include:

- Rock Hill-York County Airport;
- Northwoods Square Shopping Center;
- Dutchman Creek Middle School;

The watershed also contains several parks, including Cherry Park, Oakwood Acres, Hargett, Fewell, and Boyd Hill Recreation Center, all in the southeastern portion of the watershed.




Figure 1.23 Aerial image of watershed

- Mount Gallant Elementary School;
- Piedmont Medical Center; and
- Rolling Hills Nursery and Landscaping.

Water Supplies

The City of Rock Hill water system and wells are the sources of drinking water within the watershed. Drinking water is withdrawn from Lake Wylie and treated by the City of Rock Hill Water Treatment Plant to remove sediment, bacteria, and other contaminates before being made available for public consumption. This treatment processes results in water that exceeds DHEC and EPA quality standards. The Lake Wylie water intake is upstream of where the Big Dutchman Creek Watershed flows into the Catawba River, so activities within the watershed will not impact this drinking water source.

However, there is another water intake that is downstream from the watershed. This water intake will be impacted, both positively and negatively, by activities within the watershed. Figure 1.24 shows the locations of these water intakes.

Wells withdraw and filter groundwater. The depth of the wells combined with the impermeability of the clay soils common in the watershed help to protect the quality of well water from the impacts of human activity. There are 11 privately owned and maintained public water supply wells throughout the watershed.




Figure 1.24 Public water supply intakes near the watershed

Population & Projected Growth

÷




Figure 1.25 Graph depicting future population growth for South Carolina, York County, and the Watershed

In 2020, the Big Dutchman Creek Watershed was home to approximately 28,000 people. Because of the recent changes to U.S. Census tracts, it is not possible to accurately estimate the population within the watershed prior to the 2020 census. However, there is data available that shows the population growth in York County and South Carolina between 1970 and 2020.

Both South Carolina and York County have experienced significant population growth since the 1970s. The population in York County grew 228% between 1970 and 2020. The population in South Carolina grew 98% during the same time (U.S. Census Bureau, 1970-2020). If the population of the Big Dutchman Creek Watershed grows at the same rate as York County, then the projected 2050 population will be 39,000. These growth trends and predictions can be seen in Figure 1.25.

The additional residents in the watershed will help grow the economy of the area; however, they will need additional housing and amenities that will result in converting open space to roads, roofs, and parking lots. It will be crucial to increase efforts to protect the watershed from the hydrologic changes that could result from those land use conversions.

Local Interest in Protection & Restoration

The City of Rock Hill is significantly advancing environmental preservation, especially through its stream restoration initiatives. Several projects in this area have already been completed. In addition, the City is involved in thorough stream assessments, which help pinpoint potential sites for future restoration efforts.

The wider York County community is also engaging in conservation activities, such as the litter sweeps shown in Figure 1.26. These activities are spearheaded by York County Stormwater and Environmental Compliance, which focuses on protecting local waterbodies. In addition, several conservation organizations are leading efforts to preserve the environment within the watershed.



Figure 1.26 Volunteer litter sweep (Keep York County Beautiful)

Keep York County Beautiful

Founded via York County Ordinance No. 710 in 2010, the Keep York County Beautiful board is an affiliate of the larger Keep America Beautiful organization. They accomplish their mission of "inspiring and encouraging citizens to take personal responsibility for improving the environment of their York County community" through volunteer cleanup programs, site adoption programs, and public education. These educational outreach efforts include recycling and litter prevention presentations, promoting apartment community recycling and beautification of public spaces, and working with local businesses on waste reduction practices (York County, 2023). More information about the Keep York County Beautiful board can be found on their website and Facbook page.



Catawba Riverkeeper

Founded in 1997, the Catawba Riverkeeper's mission is to "preserve, protect, and restore the waters of the Catawba-Wateree River basin for all through education, advocacy, and engagement." This organization operates in both North and South Carolina and advocates for both the Catawba River and for those who utilize the river for livelihood and recreation.


The Catawba Riverkeeper also offers a plethora of volunteer and special events. These events include annual Riversweeps across more than 50 sites, public cleanup events, a Riverkeeper Explorers Camp, a Trash Trap Program, RiverFest, and Jam at the Dam live music event. More information about the Catawba Riverkeeper can be found on their <u>website</u> (Catawba Riverkeeper, 2023).





Rock Hill Clean & Green

This City-sponsored organization was certified as a Keep America Beautiful affiliate in 1987. It is comprised of 15 volunteers that are appointed by the City Council. Its mission is to "promote litter reduction, beautification and recycling through public awareness, education and special events designed to reach every segment of the population; to make recommendations to city government on programs, policies and codes which impact these issues." To help accomplish this mission, Rock Hill Clean & Green participates in America Recycles Day, the Earth Day Birthday, the Great American Clean-Up, and sponsors Rock Hill litter pick-ups. As a result of their dedication, Rock Hill Clean & Green won a national award for its environmental education programs among numerous other state and national accomplishments (City of Rock Hill). More information about Rock Hill Clean & Green can be found on their website.



Watershed Analysis

The South Carolina Pollution Control Act and SC Regulation 61-68: Water Quality Classifications and Standards establish a classifying system for the state's waters, assigning uses to each classification, and assigning standards that must be maintained to support those uses.

Water Quality Classification & Standards

The primary goal of these rules is to maintain waters that meet water quality standards and restore waters that do not. A water is considered impaired if it does not meet the standards associated with its water quality classification. All freshwaters (FW) in South Carolina are required to be of sufficient quality to support the uses shown in Figure 2.1.

SC Regulation 61-69: Classified Waters lists the classification and boundaries of waterbodies in South Carolina. The purpose of water quality classifications is to protect water quality as well as public health, safety and welfare. These standards also assist DHEC in making decisions about establishing pollutant limits when it issues wastewater and stormwater permits.



Figure 2.1 Uses that all freshwaters in SC should support

In the Big Dutchman Creek Watershed, all waters are classified as Freshwater (FW). Figure 2.2 summarizes some of the water quality standards associated with the FW classification.

Pollutant	Water Quality Standard
E. coli	\leq 349 CFU / 100 mL, and a geometric mean \leq 126 CFU / 100 mL for 4 samples within a 30 day period
Turbidity	\leq 25 NTUs for lakes, \leq 50 NTUs for other waters
рН	6.0 - 8.5
Dissolved Oxygen	≥ 5.0 mg/L for a daily average with no samples below 4.0 mg/L
Nonpoint Source Runoff	Allowed if uses are maintained and protected
Garbage, Ashes, Oils, & Sludge	Not allowed
Permitted Discharges of Treated Wastes	Allowed if permit conditions are met and uses are maintained and protected

Figure 2.2 Table summarizing DHEC water quality standards for Freshwater (FW)

Impairments & TMDLS & Watershed Plans

The term "303(d) list" is short for a state's list of impaired and threatened waters (e.g. stream/ river segments, lakes). The EPA requires all states to develop a list of waterbodies that do not meet water quality standards. This requirement comes from Section 303(d) of the Clean Water Act, hence the name for the list. The purpose of the list is to identify impaired waters and to identify the sourc of impairment so that corrective actions can be taken to improve water quality. EPA mandates that the 303(d) list of impaired waters be developed every two years and submitted to EPA for approval.

BASIN	HUC-12	COUNTY	STATION	DESCRIPTION	2020 IMPAIRED USE	2020 STATUS	2020 CAUSE	2022 IMPAIRED USE	2022 STATUS	2020 CAUSE	PRIORITY RANK
CATAWBA	030501030601	YORK	LCT-02	BIG DUTCHMAN CR AT MT. GALLANT RD.	NA	NOT ASSESSED	NA	REC	IMPAIRED	E. COLI	3

Figure 2.3 DHEC's 303(d) list entry for Big Dutchman Creek

The SC Watershed Atlas displays the state's water quality monitoring sites and 303(d) listed waterbodies and a wide variety of additional watershed data, including water quality classifications, floodplains, permitted discharges, and some additional information as shown in Figure 2.4. There are two water quality monitoring sites within the watershed, as shown in the Figure 2.5. The State monitors near the point where the Big Dutchman Creek flows into the Catawba River. While sampling at one point provides an efficient snapshot of the overall watershed bacterial load, including additional locations would allow the Key Partners to better pinpoint pollutant sources.




Figure 2.4 Screenshot of SC Watershed Atlas

	South Carolina develops a 303(d) list every two years for the waterbodies that fail to meet water
S	quality standards. The 303(d) list cycles begin
	on even-numbered years. In developing <u>South</u>
S	Carolina's 303(d) list, DHEC solicits and evaluates
се	all existing and readily available water quality data
)	collected over the previous 5 years.
се	
	Figure 2.3 shows the current 303(d) list entry for
nat	Big Dutchman Creek. Because the watershed was
	not assessed previously, it is not possible to tell if
	the impairment occurred recently or if the creek
	has been impaired for a long period of time.




Figure 2.5 Water quality sampling point in watershed

According to the Clean Water Act, each state must develop TMDLs (Total Maximum Daily Load) for all the waters identified on their Section 303(d) list of impaired waters, according to their priority ranking on that list. The TMDL is a calculation of the load reduction needed for a waterbody to meet its uses and assigns the load reductions required for the various pollutant sources (both point and nonpoint). TMDLs must account for seasonal variations in water quality and provide a margin of safety to account for uncertainty in predicting how well pollutant reductions will result in meeting water quality standards. TMDLs must be approved by both DHEC and the EPA.

Big Dutchman Creek has been assigned a priority rank of "3." Each of the waters listed in the 303(d) list is assigned one of the following priority ranks depending on how soon it will be addressed by a TMDL:

- 1. Current: 2022 2024
- 2. Near-Term: 2024 2026
- 3. Long-Term: After 2026

The purpose of this Watershed Plan is to bring the watershed into attainment of the water quality standards so that a TMDL will not be needed. After a water has been added to the 303(d) list, it can only be removed by either being improved to meet the water quality standard or by having a TMDL developed for it.

The status of Big Dutchman Creek as a long-term priority allows time for this Watershed Plan to be implemented and, hopefully, for the SC water quality standard to be achieved so that a TMDL will not need to be developed. This Watershed Plan not only addresses the identified cause of impairment, E. coli, but also addresses several other concerns in the watershed, including nutrients and hydrologic modification. These pollutants and goals are described below.

E. coli Description & Monitoring Data

E. coli is a shorter name for *Escherichia coli*, which is a bacteria that exists in the fecal matter of farm animals, humans, wildlife and pets, Most E, coli bacteria do not cause illness. However, there is a subset of E. coli bacteria that are pathogenic, and possibly life-threatening, as shown in Figure 2.6. The disease-causing type of E. coli can be carried by water and therefore is an important parameter to include in water quality monitoring.

E. coli is measured as colony forming units (CFU) per 100 milliliters (mL). A CFU is an estimate of the number of viable bacteria cells in a sample.

Figure 2.7 shows that the average of the DHEC sampling results from sample station LTC-02 is 1,070 CFU/100 mL, which is higher than the water quality standard of 349 CFU/100 mL of E. coli. This data indicates that reductions in E. coli will be necessary to bring the watershed into compliance with the required standard. A 30% reduction in E. coli is proposed as an appropriate adaptive goal to begin the process of achieving water quality standards in the Big Dutchman Creek Watershed.





Figure 2.7 Recent E. coli sampling results



E. coli Count in CFU/100 mL

Total Nitrogen & Total Phosphorus Description

Nitrogen and phosphorus are both nutrients, which are substances that provide nourishment that is essential for growth and maintenance of life. Although plants and animals require nutrients to survive and thrive, human activities in the watershed can contribute much higher levels of nutrients than are typically found in an undeveloped watershed. Elevated levels of nutrients in waterbodies can trigger an algal bloom, like the one shown in Figure 2.8 below. Algal blooms can be toxic to humans and animals. They also block sunlight that is needed by other aquatic plankton (small plants in the water), causing them to die and decompose, which then depletes the water of oxygen and endangers the health of the entire ecosystem (Water Science School, 2018).

The main sources of nitrogen and phosphorus in a developed watershed are:

- Fertilizers. Although fertilizer promotes plant growth, when it is improperly applied, excess nutrients can be transported to waterbodies in stormwater runoff or through ground water via infiltration.
- Human waste. Improperly functioning septic systems and sanitary sewer overflows can cause human waste and its associated nutrients to be transported to waterbodies in stormwater runoff.
- Animal waste. When pet waste is not cleaned up and properly disposed of, or if livestock are not separated from streams, animal waste and its associated nutrients can reach waterbodies through direct deposition or stormwater runoff.
- Atmospheric deposition. Emissions from vehicles contain nitrogen compounds that can be deposited on land and carried to waterbodies in stormwater or deposited directly in waterbodies. Phosphorus can also be carried by the atmosphere and deposited on the land and water.


In this Watershed Plan, nitrogen is measured as Total Nitrogen (TN). TN includes several different nitrogen compounds such as nitrate-nitrate (NO₂ and NO₃ in fertilizer and car emissions), ammonia (NH₃ in fertilizer and animal waste), and organic nitrogen (from plant and animal debris). TN compounds are frequently dissolved in water and can be removed by plant uptake or chemical processes. Figure 2.9 shows the complexities of the nitrogen cycle.

Phosphorus is measured in the Watershed Plan as Total Phosphorus (TP). TP includes several different inorganic compounds as well as organic phosphorus from plant and animal debris. TP is usually easier to remove from stormwater than TN because many of the phosphorus compounds bind with sediment, allowing them to be filtered or settled out. Figure 2.10 shows the phosphorus cvcle.

Although the Big Dutchman Creek Watershed is not currently impaired for TN and TP, the goal is to control and reduce the existing sources of nutrients and prevent new ones so that nutrients will not become a cause of impairment to this watershed in the future as the watershed continues to develop.



Figure 2.8 Photo of algal bloom in York County, SC (McAdams)



Hydrologic Impacts

The Big Dutchman Creek Watershed is not currently impaired for hydrologic impacts to aquatic life. However, the goal of this Watershed Plan is to prevent "failure to support aquatic life" as a cause of impairment in the future as the watershed continues to develop. As watersheds urbanize, several hydrologic changes occur. Development raises the elevation of low areas, which previously provided storage, and paves over pervious areas, which previously provided opportunities for infiltration. The addition of curb and gutters with storm sewer systems quickly directs more runoff to streams and lakes. Left unchecked, hydrologic impacts cause serious damage to the physical and biological integrity of the receiving stream, such as the flooding and erosion depicted in Figure 2.11 and 2.12. These impacts include:

- Increased speed and volume of flow within the stream compared to pre-development conditions;
- Increased frequency of flooding;
- · Wider stream channels due to increased storm flows. Streambanks are undercut and slump into the channel;
- Weakened trees along the streambank due to exposed roots. When these trees fall, a second phase of bank erosion can be triggered;
- Elimination of aquatic habitat through sedimentation;
- Diminished groundwater flow to streams, causing less flow to streams between storm events;
- Decreased aquatic biodiversity as sensitive species are reduced or eliminated;
- Substantially increased pollutant volume entering the stream system; and
- Increased stream temperatures, which can further harm aquatic plants and animals.



Figure 2.11 River and creek flooding (Independent Mail)



Figure 2.12 Streambank erosion caused by hydrologic impacts (Clemson University)

As the Big Dutchman Creek Watershed continues to develop, the volume and intensity of runoff will increase. This increase will impact the physical characteristics of streams as described above. Artificial structures, such as bridges or culverts, may restrict water flow, and cause stream erosion. Other hardened structures, such as walls and riprap, transmit more energy downstream than vegetated streambanks, increasing erosive stresses on weaker areas of the streambank.


Objective Statement

The main objective of this Watershed Plan is to propose management measures that will lead to a sufficient reduction of E. coli bacteria within the watershed so that Big Dutchman Creek will meet the required water quality standards. Additional objectives identified by the Key Partners and concerned citizens are to reduce nutrients and hydrologic impacts from development.

More specifically, this Watershed Plan seeks to implement a variety of practical and cost-effective management measures that, when implemented together, achieve the following:

- 1. Reduce bacteria and nutrients from humans (numeric goal: 30% reduction in E. coli and 25% reduction in TN and TP):
- 2. Reduce bacteria and nutrients from animals (numeric goal: 30% reduction in E. coli and 25% reduction in TN and TP):
- and
- 4. Increase education and outreach (no numeric goal).

3. Reduce hydrologic impacts from development (numeric goal: provide at least 5 measures to restore hydrology in the next 5 years while increasing hydrologic protection on new development projects);



Pollutant Sources

This section addresses Element A – identify causes and sources of pollution and the first part of Element B - estimate pollutant loading.

Summary of Impairments, Causes, Sources & Impacts

Big Dutchman Creek is on the 303(d) list based on water quality monitoring data showing levels of E. coli that significantly exceed the SC water quality standard. Therefore, addressing the potential sources for E. coli is a focus for this Watershed Plan. Key partners and involved citizens have identified several concerns beyond E. coli to address in this Watershed Plan: Total Nitrogen (TN), Total Phosphorus (TP), and hydrologic impacts from impervious surfaces. The causes, sources, and waterbody impacts associated with each of the impairments is described in Figure 3.1.

Impairment	Causes	Potential Sources	Waterbody Impacts	
	Point Sources	Sanitary sewers leaks/ overflows	Health risks to animals	
E. coli (from 303d list)	Septic Systems	Unmaintained and failing septic systems	 Potentially serious or even fatal health risks to humans Loss of recreational resources 	
	Other Nonpoint Sources	Pet waste, geese, wildlife, livestock		
	Point Sources	Sanitary sewer leaks/ overflows	 Algal blooms Health risks to humans and animals Loss of recreational resources 	
TN and TP (from observations)	Septic Systems	Unmaintained and failing septic systems		
	Other Nonpoint Sources	Excessive fertilizer, pet waste, geese, wildlife, livestock		
Hydrological (from observations)	Nonpoint Sources	Increased impervious cover	 Eroded streambanks Loss of riparian habitat and property Risks to human health and safety 	

Figure 3.1 Table summarizing the impairments, causes, sources and impacts in the watershed



Figure 3.2 Point source pollution example (Encyclopædia Britannica, 2023)

What is Point Source Pollution?

Point source pollution is discharged from a discrete location, such as the end of an outlet pipe as seen in Figure 3.2. Wastewater treatment plants and industries are required to have a discharge permit from DHEC to discharge treated wastewater. No one is allowed to discharge untreated wastewater, either intentionally or accidentally.

What is Nonpoint Source Pollution?

Unlike point source pollution, nonpoint source pollution does not have a discrete discharge point. Instead, nonpoint sources are areas where pollutants are present on land and are carried away with stormwater runoff, as illustrated in Figure 3.3. Examples of nonpoint source pollution include nutrients from fertilizers applied to landscaped areas, E. coli from pastures, oil and grease from roadways, and sediment from construction sites.




Figure 3.3 Nonpoint source pollution example (Three Lakes Association, 2017)

Sanitary Sewer Overflows (SSOs)

Within the Big Dutchman Creek Watershed, there are no discharges of either treated or untreated wastewater from wastewater treatment plants. However, there have been issues with sanitary sewer lines that have caused releases of E. coli, nutrients, sediment, and solid waste. Sanitary sewer systems collect and transport domestic, commercial, and industrial wastewater to treatment facilities. Occasionally, releases of raw sewage known as sanitary sewer overflows (SSOs) can occur. SSOs can contaminate surface waters, causing serious water quality problems, and can back up into homes, causing property damage and threatening public health.

Possible causes of SSOs include:

- Blockages;
- Line breaks:
- Construction activities;
- Root intrusion;
- Lack of proper maintenance;
- Vandalism; and
- Stormwater inflow and infiltration that overloads the system.

There are two types of SSOs: main line and service line. Main line SSOs occur from a larger sewer line that collects and carries untreated wastewater from many households or businesses to the wastewater treatment plant. Service line SSOs occur from a smaller line that carries wastewater from a single property to the main line. Figure 3.4 shows the difference between main and service lines.

Since 2020, there have been two main line SSOs in the Big Dutchman Creek Watershed (DHEC 2023). In addition to the main-line SSOs, there have been approximately 500 service line SSOs in the watershed since 1996 (Rock Hill GIS, 2023). The specific locations of the main line SSOs are shown in Figure 3.5. The service line SSOs are shown as a heat map.

Unlike main line SSOs, service line SSOs are often present for an extended time before the property owner notices them. Some of the signs that a service line is failing include sewage backup and soggy areas in the yard, foul odors, foundation cracks, and lush areas of green grass growth above the sanitary sewer line. It is important for property owners to know the location of their sanitary service lines and to understand the signs of a potential SSO so they will be able to take swift action before an SSO damages their property or becomes a significant source of E. coli and nutrients.




Figure 3.5 Main line SSOs (points 1 and 2) and service line SSOs (heat map) in watershed

1	Date	5/18/2023
	Discharge	10,150 gallons
	Cause	Uprooted tree broke terra cotta sewer lin
	Remediation	Debris removed & pipe replaced with ductile iron




Figure 3.4 Sanitary sewer main line and service line in a typical residence (City of Fargo, North Dakota)

e	_	
n	e	

Date	6/2/2023
Discharge	9,600 gallons
Cause	Grease blockage
Remediation	Line cleaned & lime applied to area

Septic Systems in Watershed

A septic system consists of a septic tank and a drain field. Wastewater from the household flows into the septic tank, where solids settle at the bottom. The remaining wastewater flows into the drain field, where it is released into the soil through a series of perforated pipes. The soil's physical properties filter out particles, while the microorganisms in the soil break down harmful substances like nitrogen, phosphorus, and pathogens such as E. coli bacteria. The effectiveness of a septic system depends on the soil's ability to absorb and filter the wastewater and the proper maintenance of the septic system.

When septic systems fail, untreated wastewater can seep into the groundwater or flow to streams and become a source of E. coli and nutrients. The EPA has identified malfunctioning septic systems as one of the top five sources of groundwater

contamination in the country, highlighting the need for proper installation, regular maintenance, and periodic inspections to ensure their effective and safe operation (Gibb, 2022).

As depicted in Figure 3.6, approximately 3,700 parcels within the watershed are estimated to be served by septic systems, representing approximately 27% of the total parcels. This estimate is based on the City of Rock Hill's sanitary sewer data because accurate septic system data is not available. This plan recommends the Key Partners generate precise septic system location and condition information. Reliable data is needed for both pollutant modeling and for community outreach and education.




Figure 3.6 Parcels with no sanitary service, presumed to have septic systems in watershed




Figure 3.7 Diagram of a septic system (Minnesota Pollution Control Agency 2023)

Figure 3.7 shows how a typical septic system functions. The most clear sign of a septic system failure is a sewage backup that occurs when the tank is clogged or full. Other signs of septic system failures include algal blooms in nearby lakes, slow moving drains, bright green or soggy grass in the yard, standing water, and bad odors. When a septic tank becomes clogged, it is usually necessary to have it pumped out as shown in Figure 3.8.



Figure 3.8 A septic system pump out (Vac-Tec Septic & Water LLC)


Land Uses in Watershed (acres)

Nonpoint Sources within the Watershed

In the Big Dutchman Creek Watershed, pollution from nonpoint sources far exceeds pollution from point sources. This is also true for most watersheds because the combined volume of stormwater runoff is greater than discharges from wastewater treatment plants, SSOs, and failing septic systems. Some of the stormwater in the watershed is treated in stormwater BMPs, but there is a significant amount of stormwater that enters the streams and impoundments without treatment.

Urban development alters the hydrology and water quality of streams. Roads, parking lots, and buildings increase the impervious cover and restrict the infiltration of precipitation. As a result, stream flows in urban areas often rise rapidly after a rainfall event. This can cause erosion of stream beds and banks and degrade fish spawning and feeding habitats. Other impacts are shown in Figure 3.9. The most common sources of E. coli and nutrients in the watershed are fertilizers, pet waste, geese, wildlife, and livestock.

The most prevalent land use in the watershed is urban development which accounts for about 77% of its overall area. Figure 3.10 shows the relative amounts of each land use type while Figure 3.11 shows the dispersal of land use types throughout the watershed.






Figure 3.10 Graph summarizing land uses in the watershed





Figure 3.9 Figure summarizing impervious surface impacts

Figure 3.11 Land uses in watershed



Pollutant Loading Estimate

The results of the analysis of the pollutants from each source are shown in Figure 3.12 below. It demonstrates that point sources and failing septic systems are relatively small contributors to the overall amount of E. coli, TN, and TP contributed compared to nonpoint sources in the watershed. Nonpoint sources are the largest contributors because they cover all 11,360 acres of the watershed. High density, single family residential development is the single largest contributor of nonpoint source pollutants since it is the most common land use in the watershed and has a relatively high pollutant loading rate. The highest pollutant loading rates are from multifamily residential and commercial development; however, these are less common land uses in the watershed and therefore do not have as significant of an impact overall in the watershed.




Figure 3.12 Pollutant source estimate graph

The estimated total loadings of the pollutants of concern to the Dutchman Creek Watershed are shown in Figure 3.13.

E. coli Total Load	TN Total Load	TP Total Load
(BCFU/year)	(lb/yr)	(Ib/yr)
53,063	63,630	9,430

Figure 3.13 Pollutant loading estimate

The estimates of pollutant loading were calculated as follows:

Main Line SSOs: The estimated number of sewer spills annually (0.5) was multiplied by the average volume of the spill (9,875 gallons). Typics concentrations of E. coli, TN and TP found in literature were applied to the estimated volume of main line SSOs to estimate the annual pollutant loads.

Service Line SSOs: The estimated number of service line SSOs annually (18.5) was multiplied by DHEC's loading rate factor for failing septic systems (21.09 BCFU per system), because service line SSOs contribute similar volumes and E. coli loading rates as failing septic systems. Typical concentrations of TN and TP found in literature were applied to the service line SSOs to estimate the annual nutrient loads.

Failing Septic: It was estimated that one tenth of the number of septic systems in the watershed (370) are failing. This number was multiplied by DHEC's loading rate factor for failing septic systems (21.09 BCFU per system). Typical concentrations of TN and TP found in literature were applied to the failing septic systems to estimate the annual nutrient loads.

е

al	Nonpoint Sources: Estimating the pollutant loading from the nonpoint sources was a multistep process:
of	 The areas of each type of land use within the watershed were determined using GIS data, parcel data, and aerial photography (see Figure 3.14);
	 To estimate E. coli loads, DHEC loading rate factors were applied to each type of land use;
ed	 To estimate the TN and TP loads from the land uses, the North Carolina Stormwater Nitrogen and Phosphorus (SNAP) Tool was used;
0	• The SNAP Tool requires that each land use be broken into the following land covers: roof, roadway, parking/driveway/sidewalk, forest, and landscaped area/grass. The land covers associated with each type of land use were estimated using aerial images of developments within the watershed;
a	 For each land use, the estimated land covers were input into the SNAP Tool. The SNAP Tool produced the nutrient loading rate for each of the land uses in pounds/ acre/year (see Figure 3.15);
ıg	 The loading rates in pounds/acre/year estimated using the SNAP tool were multiplied by the acres of each land use to estimate the pounds/year contributed by each land use.

Pollutant Loading Rates for Watershed Land Uses


Note: The pollutant loading rate is the contribution of the pollutant per acre. The total pollutant load in Figure 3.12 reflects the pollutant loading rate times the acres in each land use.


0 2 1,000 5,000 6,000 0 2,000 3,000 4,000 LD Single Family LD Single Family 1,331 0.6 HD Single Family HD Single Family 5,064 0.7 Multi-Family Multi-Family 263 1.0 2.0 Commercial Commercial 932 1.1 0.1 Road Road 1,135 0.9 Pasture Pasture 435 Grass 1,020 Grass 1.0 1.4 Forest 1,178 Forest 1.0 0.0

Figure 3.15 Pollutant loading rates for watershed land uses

Figure 3.14 Watershed land uses

Watershed Land Uses (acres)





oad Reductions

This section addresses the second part of EPA's Element B – estimate the expected load reductions.

Watershed Plan Review

The watershed is impaired due to exceedances of E. coli bacteria in one sampling location just upstream of where Big Dutchman Creek discharges to the Catawba River. DHEC has rated this impairment as Priority 3, meaning they do not intend to develop a TMDL for E. coli until after 2026. In addition to E. coli, the Key Partners and citizens in the watershed reported concerns over excessive TN and TP.

The objectives of this Watershed Plan are to:

- Reduce bacteria and nutrients from humans;
- Reduce bacteria and nutrients from animals;
- Reduce hydrologic impacts from development; and
- Increase public education.

To achieve these goals, nearly all the pollutant sources in the watershed will require some level of reduction. Figure 4.1 illustrates the overall pollutant reduction goals within the watershed. The prevalence of each pollutant source and a reduction estimation for each management measure are shown in Figure 4.2.

The expected pollutant removals from individual management measures, along with a description of each measure, are detailed in Section 5. To address each of the nonpoint sources of pollution and meet the objectives outlined in Figure 4.1, a combination of the proposed management measures will be necessary.

For point sources and failing septic systems, the pollutant removals were estimated to be 100%, as resolving these issues would completely eliminate the pollutant source. Therefore, even though these sources were not large contributors of pollutants, this Watershed Plan proposes to address a high percentage of these sources.

For nonpoint sources, this Watershed Plan suggests targeting a high percentage of residential developments and grassed areas, and half of the commercial properties. As the next section will show, management measures on pasture are very cost-effective and thus it is suggested to implement agricultural measures on all or nearly all of this land use.

Targets are not provided for forest land because this is the natural land use and contributes a very low concentration of pollutants.

Numeric Pollutant Reduction Goals for this Plan					
E. coli Total Load (BCFU/year)	TN Total Load (lb/yr)	TP Total Load (lb/yr)			
30%	15%	30%			

Figure 4.1 Numeric pollutant reduction goals for this plan

Total	Type of	Units	E. coli R	emoved	TN Rei	moved	TP Rei	noved
Units	Unit	Treated	(%)	(BFCU/ yr)	(%)	(lb/yr)	(%)	(lb/yr)
ces and	Septic S	ystems						
0.5	SSOs/ year	100%	100%	4	100%	1	100%	0
18.5	SSOs/ year	80%	100%	312	100%	86	100%	23
370		75%	100%	5,854	100%	1,606	100%	439
Sources								
1,331	acres	75%	20%	655	20%	811	25%	137
5,064	acres	75%	20%	4,018	20%	4,185	25%	646
263	acres	75%	40%	584	20%	352	50%	103
932	acres	50%	20%	184	20%	880	50%	254
1,135	acres	30%	20%	4	20%	648	20%	61
435	acres	90%	90%	1,987	30%	685	75%	840
1,020	acres	75%	60%	2,589	35%	648	50%	398
1,178	acres	0%	0%	0	0%	0	0%	0
al Load Rei	al Load Removed		16,191		9,902		2,901	
age of Loa	d Remove	d	30	0%	15	5%	30	0%

	Total	Type of	Units	E. coli R	emoved	TN Rei	noved	TP Rer	noved
	Units	Unit	Treated	(%)	(BFCU/ yr)	(%)	(lb/yr)	(%)	(lb/yr)
Point Sourc	ces and s	Septic S	ystems						
Main Line SSOs	0.5	SSOs/ year	100%	100%	4	100%	1	100%	0
Service Line SSOs	18.5	SSOs/ year	80%	100%	312	100%	86	100%	23
Failing Septic	370		75%	100%	5,854	100%	1,606	100%	439
Nonpoint S	ources								
LD Single Family	1,331	acres	75%	20%	655	20%	811	25%	137
HD Single Family	5,064	acres	75%	20%	4,018	20%	4,185	25%	646
Multi-Family	263	acres	75%	40%	584	20%	352	50%	103
Commercial	932	acres	50%	20%	184	20%	880	50%	254
Road	1,135	acres	30%	20%	4	20%	648	20%	61
Pasture	435	acres	90%	90%	1,987	30%	685	75%	840
Grass	1,020	acres	75%	60%	2,589	35%	648	50%	398
Forest	1,178	acres	0%	0%	0	0%	0	0%	0
Total	Load Rer	noved		16,	191	9,9	02	2,9	01
Percenta	ge of Loa	d Remove	d	3()%	15	5%	30)%

Figure 4.2 Point source, septic system, and nonpoint source pollutant load removal




Descriptions of Management Measures This section addresses EPA's Element C – describe management measures that will

achieve load reductions and targeted critical areas.

Summary of Objectives & Management Measures

Figure 5.1 presents the four objectives of this Watershed Plan, each supported by 5-6 management measures aimed at fulfilling these objectives. This section details the management measures associated with Objectives 1, 2, and 3. For management measures related to Objective 4, 'Increase Education & Outreach,' refer to Section 9 of this plan. A summary of pollutant removal effectiveness and implementation costs for each management measure is presented in Figure 5.36 at the end of this section.



Provide lawn care education Provide educational signage Increase coverage of water quality in the media Expand existing engagement programs

Figure 5.1 Diagram of watershed objectives & management measures

Objective 1 Measures

1a. Repair, Replace, or Connect Failing Septic Systems

The effectiveness of a septic system depends on the soil's ability to absorb and filter the wastewater and the proper maintenance of the septic system. When a septic system fails, untreated wastewater can seep into the groundwater or flow to streams and become a source of E. coli and nutrients. The EPA has identified malfunctioning septic systems as one of the top five sources of groundwater contamination in the county, highlighting the need for proper installation, regular maintenance, and periodic inspections to ensure their effective and safe operation. Repairing or replacing these failing systems reduces the E. coli, nitrogen, and phosphorus load to local waterbodies (Gibb, 2022).




Figure 5.2 Septic system fixes at a glance *University of North Carolina (2015) **Forbes (2023)

1b. Install Rain Gardens

Rain gardens offer an aesthetically pleasing solution for stormwater management and are suitable for both residential and commercial environments. These gardens temporarily hold stormwater, allowing it to be naturally treated by native plants and soil infiltration.




Figure 5.4 Rain gardens at a glance *Interstate Commission on the Potomac River basin (2024)

Objective 1 measures reduce the bacteria & nutrient pollution from human sources.

If the option is available, property owners facing issues with their septic systems should consider the benefits of connecting to the City of Rock Hill's sanitary sewer system. Sanitary sewers are less likely to fail than septic system, and even in cases of malfunction, the impact is often more contained and managed quickly to minimize environmental impacts. The Manchester Wastewater Treatment Plant is equipped with advanced technologies and processes to treat and purify the water to a much higher standard

than what a septic system can achieve. The treated water is safe enough to be released into rivers, lakes, or even used for irrigation.

Cost	Priority Area
System Connected* er System Fixed**	Homes with Septic Systems



Figure 5.3 Rain Garden (EPA, 2014)

Cost	Priority Area
t² (Residential)* t² (Commerical)*	Residential and Commerical Areas

1c. Implement Sanitary Capital Improvement Plan

Damaged sanitary sewer lines present a significant environmental hazard because they discharge raw sewage directly into the ground and surface waters, and often are sited in low areas adjacent to surface waters. Sanitary sewer overflows (SSOs) are quickly addressed by City of Rock Hill staff, who repair the breaks and mitigate environmental impact. The City's implementation of its Capital Improvement Plan (CIP) 2023-2028 will help to address the most urgent sewer infrastructure repairs and replacements and reduce the risk of future SSOs.



Figure 5.5 Repaired section of sanitary sewer line (Paradise Plumbing)

	Pollutant Removal Effectiveness		Cost	Priority Area	
E. coli	TN	TP			
			\$2.5 Million over 5 Years*	Homes with Septic Systems	

Figure 5.6 CIP implementation at a glance *City of Rock Hill (2023)

Remove Litter from Streams

Trash in streams is unsightly and can also contribute nutrients and other pollutants and provide food sources for E. coli bacteria. For example, plastic waste breaks down into microplastics that are ingested by a wide range of animals and harm their health. The current stream cleanups organized by the Catawba Riverkeeper and Keep York County Beautiful can be continued and expanded to address this issue.



Figure 5.7 Litter clogs the Catawba River (Random Connections)

	Pollutant Removal Effectiveness		Cost	Priority Area	
E. coli	TN	ТР			
	0	0	\$8,065 per Ton of Litter*	All Streams	

Figure 5.8 Stream litter removal at a glance *Axios (2023)

1e. Remove Litter from Streets

Compared with stream cleanups, removing litter from streets is significantly more efficient. On streets, volunteers collecting litter can stay dry and avoid the hazards of working in a stream area. Removing litter before it reaches waters avoids disruption and damage to aquatic ecosystems. Rock Hill Clean & Green organizes and promotes street cleanup events; these efforts can be continued and enhanced.

> Figure 5.9 Clean & Green volunteers remove trash from streets (Rock Hill Clean and Green)

Pollutant Removal Effectiveness			Cost	Priority Area
E. coli	TN	ТР		
•	0	0	\$1,000 per Ton of Litter Removed*	Primary & Secondary Roads

Figure 5.10 Street litter removal at a glance *York Daily Record (2019)

1†. Sweep Streets

Streets collect debris, including pet/wildlife waste, leaf litter, yard clippings, trash, and soil, that can be a source of E. coli and nutrients. During storm events, streets become conveyances that carry this debris directly to the stream through the storm drainage system. Street sweeping is an efficient way to prevent these pollutants at the source. Ideally, a regular street sweeping schedule could be maintained for primary and secondary roads. Some communities repurpose the collected debris for beneficial uses, such as fill material (EPA, 2021).

	Pollutant Removal Effectiveness		Cost	Priority Area		
E. coli	TN	ТР				
		•	\$94 per Mile of Street Swept*	Primary & Secondary Roads		

Figure 5.12 Street sweeping at a glance *Minnesota Pollution Control Agency (2023)





Figure 5.11 Street sweeper (North American Power Sweeping Association)

Convert Dry Detention Basins to Stormwater Wetlands (1g.)

Dry detention basins have historically been a popular choice for urban stormwater management due to their ability to provide effective flood control over large areas. However, they are not very effective at removing nutrients or E. coli from stormwater. Transforming existing dry detention basins into stormwater wetlands is becoming a popular solution. Since the land for these basins is already graded and designated for stormwater management; conversion only requires a modification to the outlet structure and

the addition of wetland plantings. Stormwater wetlands offer substantial improvements over dry detention basins in terms of water quality enhancement. As water flows through the wetland, pollutants are naturally filtered out, both through settling and through biological processes inherent to the wetland ecosystem. Moreover, stormwater wetlands add significant aesthetic value to an area, creating visually appealing landscapes as opposed to the often barren appearance of dry detention basins (EPA, 2005).

	Pollutant Removal Effectiveness		Cost	Priority Area
E. Coli	TN	ТР		
•			\$165,000 per Conversion*	Existing Dry Detention Ponds

Figure 5.13 Dry detention basin conversions at a glance *Fairfax County (2005)



Figure 5.14 Stormwater wetlands clean water well and look attractive (McAdams)

Objective 2 Measures

Implement a Goose Egg Addling Program

Goose fecal matter presents a serious water quality concern due to its transmission of E. coli, TN and TP, usually directly adjacent to or in a waterbody. Addressing the issue of goose population control in a humane and effective manner is challenging. The most humane and effective strategy is egg addling, a process that prevents eggs from developing into goslings. This method involves treating eggs, preferably those that are 14 days old or younger with 100%




Figure 5.15 Goose egg addling at a glance *University of Nebraska (2010)



Figure 5.16 Oiling goose eggs prevents embryo development (Star Tribune)

Objective 2 measures reduce the bacteria & nutrient pollution from animal sources.

vegetable oil. The oil application obstructs the tiny pores on the eggshell, stopping the embryo's development without harming the adult geese. This approach is more effective than simply destroying the eggs as geese will often renest and lay more eggs if their initial clutch is destroyed. Egg addling, therefore, presents a sustainable and ethical solution to managing goose populations and mitigating their environmental impact on waterbodies (USDA, 2022).

Cost	Priority Area
r Addled Nest*	Impoundments

Provide Alternative Water Sources on Pastureland 2b

Providing alternative water sources for livestock on pasturelands supports both animal health and water quality protection. Traditionally, livestock wander down to the stream when they need water; however, this leads to contamination from animal waste and increased bank erosion due to animal traffic. By separating the animals from streams and offering them a distinct, clean

water supply, several benefits are achieved. For the livestock, the alternative water is generally cleaner and safer compared to surface waters, potentially improving their health. Moving the water source around the grazing area can also lead to more efficient and uniform grazing patterns, as livestock tend to congregate near water sources.

	Pollutant Removal Effectiveness		Cost	Priority Area	
E. coli	TN	ТР			
	•		\$37 per Acre of Pasture Served*	Pasture	

Figure 5.17 Alternative water sources at a glance *ŪSDA, 2000



Figure 5.18 Cow conference by the water cooler (PGG Wrightson)



Fencing off streams to keep livestock out, combined with providing alternative water sources, is an effective dual strategy. It not only preserves water quality by preventing livestock from accessing natural streams, but also ensures that the animals' need for drinking water is adequately met.

Pollutant Removal Effectiveness			Cost	Priority Area
E. coli	TN	TP		
		•	\$2 per linear foot of fence*	Pasture

Figure 5.20 Livestock exclusion at a glance *lowa State University (2012)




Figure 5.21 Five reasons to keep livestock out of rivers (The Freshwater Trust)



Figure 5.19 Livestock fencing (Western Pennsylvania Conservancy)

Provide Pet Waste Stations 2d

Like goose waste, pet waste is a significant contributor to E. coli and nutrient pollution, particularly in urban and suburban areas. Remarkably, a single pet waste station can capture up to 2,250 pounds of dog waste annually, substantially reducing the pollutants entering the watershed. These stations are inexpensive to install and offer an opportunity for public education, reminding pet owners to dispose of their pets' waste properly to preserve the cleanliness and safety of public spaces and water bodies (City of Kirkland, 2020).



Figure 5.22 Pest waste stations keep the grass fun for all (Recycle Away)

Pollutant Removal Effectiveness			Cost	Priority Area
E. coli	TN	TP		
		•	\$200 per Station*	Parks

Figure 5.23 Pet waste stations at a glance *Bow Wow Waste (2024)

Increase Catch 26 **Basin Cleaning**

As their name implies, catch basins often capture debris such as pet/wildlife waste, leaf litter, yard clippings, trash and soils, all of which are sources of E. coli and nutrients to streams. Regular cleaning of catch basins removes captured material and associated pollutants and has the added benefit of preventing blockages in the storm drainage system that can lead to flooding.

> Figure 5.24 Cleaning dirty catch basins in the Big Apple (NYC Environmental Protection)



Pollutant Removal Effectiveness			Cost	Priority Area
E. coli	TN	TP		
•		•	\$300 per Basin Cleaned*	Paved Roads

Figure 5.25 Catch basin cleaning at a glance *FEMA (2020)

Objective 3 Measures

Objective 3 measures reduce the hydrologic impacts caused by development. Although the primary purpose of these measures is to address the increases in volume and velocity of stormwater that occurs when the natural landscape is replaced with roofs, roads, and other hardened surfaces, they also have some benefits for reducing E. coli and nutrients.

Disconnect Household Downspouts

Downspouts typically function by channeling stormwater from roofs away from structures. In many instances, downspouts are directly connected to the storm drainage system through pipes or they discharge the water onto paved surfaces that discharge to the storm drainage system. Property owners with directly connected downspouts can disconnect their storm drains and instead direct the stormwater from the roof into gardens or lawns, where most of the water will infiltrate into the soil. This practice reduces the volume of stormwater

Pollutant Removal Effectiveness			Cost	Priority Area
E. coli	TN	TP		
0	0	0	\$100 per Downspout Disconnect *	Residential Areas

Figure 5.26 Downspout disconnection at a alance. *Nick's Window Cleaning (2017)



Figure 5.27 Downspout disconnect allows stormwater to recharge groundwater (The Pocket)

and helps to reduce the burden on stormwater pipes and channels. In addition, disconnecting downspouts enhances water quality because the stormwater is filtered through the soil, which removes E. coli and nutrients. Disconnecting downspouts can also provide a water source for landscaping (particularly if the homeowner chooses to store the stormwater in a rain barrel so it will be available after storm events). Overall, disconnecting downspouts is a simple yet effective step towards sustainable water management and conservation at the household level (Ruiz et al, 2017).

3b. **Provide Flood Attenuation & Storage**

The proliferation of streets, homes, and other infrastructure within the watershed increases the presence of impervious surfaces like asphalt, concrete, and roofs that do not absorb stormwater. Consequently, rainwater that would naturally percolate into the ground instead rapidly flows over these hard surfaces to streams that are overwhelmed by the volume and velocity of flows

that are reaching them. Flood attenuation and storage mechanisms, such as retention ponds, can be implemented to capture and temporarily hold stormwater, allowing it to be released gradually over time. This controlled release also provides some pollutant removal through a natural settling processes.

Pollutant Removal Effectiveness			Cost	Priority Area
E. coli	TN	TP		
	•	•	\$70,000 per Acre of Impervious Treatment*	Entire Watershed

Figure 5.28 Flood attenuation & storage at a glance *U.S. EPA (2021)




Figure 5.29 Retention pond components and operation (City of Naperville, Illinois)

Restore and Enhance Stream Buffers 3c.

Stream buffers are the areas surrounding surface waters that typically extend 50 to 150 feet from the bank. Protecting buffers from development is required by the jurisdictions in this watershed because they have significant environmental benefits. Their primary function is to stabilize the stream bank from erosion and protect developed areas from flooding. The roots of the plants in a stream buffer filter and take up E. coli and nutrients and bacteria before they reach the




Figure 5.30 Before and after buffer restoration (Urban Ecosystems)




Figure 5.31 Stream buffer restoration and enhancement at a glance *American Water Resources Association (2012)

- surface water areas. Areas that lack vegetation often experience accelerated streambank erosion, resulting in steep and sheer banks. These conditions not only degrade the aquatic habitat but also hinder access to the water for both
- people and wildlife. Stream buffer restoration and enhancement involves removing impervious surfaces from the buffer, grading eroded areas if needed, and providing native plantings.

Cost	Priority Area
per Linear Foot ffer Restored*	Poorly Vegetated Buffers
1	

3d. **Restore Eroding Streams**

After a watershed is developed, streams are subject to higher velocities and volumes of stormwater, resulting in the erosion of streambanks and loss of aquatic habitat. In addition, eroding streambanks themselves can become a source of sediment pollution. Stream restoration involves creating a new structure for a stream system that better matches the characteristics of the watershed. Restoring streams reduces stream bank erosion by diminishing the energy of flowing water, which lessens the erosive force exerted on the banks. Stream restoration projects can also have a cooling effect by increasing vegetation and reducing sedimentation. During a restoration project, the stream bed and floodplain are usually regraded so that water can disperse over the floodplain during large storm events. This dispersion reduces the velocity of surface water, which minimizes erosion and improves the stream's resilience to large storm events. Stream restoration projects also include removing invasive species and planting native plant species which enhances the removal of E. coli and nutrients.

	itant Remo fectivenes		Cost	Priority Area
E. coli	TN	ТР		
0		•	\$850 per Linear Foot of Stream Restored*	Eroded Streams

Figure 5.32 Eroding stream restoration at a glance *American Water Resources Association (2012)



Figure 5.33 Before and after, Methodist University stream restoration (McAdams)

Restore Floodplains 3e.

Floodplains offer a multitude of services that include flood protection, erosion control, and habitat for diverse wildlife. However, the development of many floodplains has significantly impaired their capacity to deliver these benefits. Floodplain restoration involves restoring a stream's floodplain through voluntary buyouts of frequently flooded properties within the






Figure 5.34 Effectiveness of floodplain restoration *McAdams

Pre-Restoration



Post-Restoration

Ecologically Functional Floodplain




floodplain and regrading of the floodplain so it can receive water from the stream when it overflows its banks. Floodplain restoration projects also include planting native species to strengthen the ecological integrity of these areas and bolster their resilience against erosive forces (National Wildlife Federation). The plantings remove TN and TP and reduce vulnerability to flooding.

Cost	Priority Area
00 per acre of plain restored*	Degraded floodplains

Figure 5.35 Diagram of a floodplain & stream restoration (River Floodplain Restoration)

	Pollutan	t Removal Effe	ctiveness			
Management Measures	E. coli	TN	TP		Cost	Priority Area
Reduce Bacteria + Nutrients from Humans						
				\$1,775	per system fixed	
Repair, replace, or connect failing spetic systems				\$2400	per system connected	Homes with septic systems
				\$4	per square foot (residential)	
Install rain gardens				\$25	per square foot (commerical)	Residential & commerical areas
Implement Rock Hill's wastewater CIP				\$2,500,000	per fiscal year 2025-2028	Main sanitary sewer lines
Remove litter from streams		0	0	\$8,065	per ton of litter removed	All streams
Remove litter from streets		0	0	\$1,000	per ton of litter removed	Primary & secondary roads
Sweep streets				\$94	per mile of street swept	Primary & secondary roads
Convert dry detention ponds to wetlands				\$165,000	per conversion	Existing dry detention ponds
Reduce Bacteria & Nutrients from Animals						
Implement goose egg addling				\$60	per addled nest	Impoundments
Provide alternative water sources on pastureland				\$37	per acre of pasture served	Pasture
Exclude livestock from streams with fencing				\$2	per linear foot of fence	Pasture
Proivde pet waste stations				\$200	per pet waste station	Parks
Increase catch basin cleaning				\$300	per basin cleaned	Paved roads
Reduce Hydrologic Impacts of Development						
Disconnect household downspouts	0	0	0	\$100	per downspout disconnected	Residential areas
Provide flood attenuation & storage				\$70,000	per acre of impervious area treated	Entire watershed
Restore and enhance stream buffers	0			\$850	per linear foot of buffer restored	Poorly vegetated buffers
Restore eroding streams	0			\$850	per linear foot of stream restored	Eroded streams
Restore floodplains	0			\$15,000	per acre of floodplain restored	Degraded floodplains

Figure 5.36 Pollutant removal and implementation cost estimate table







Climate Change Considerations

Temperature Increases

Average air temperatures within the Big Dutchman Creek Watershed were determined by using data from the National Oceanic and Atmospheric Administration (NOAA) monitoring station located at Winthrop University, which is the closest air temperature monitoring station. Since its inception in 1942, this station has been collecting weather and climate data. Figures 6.1-6.3 show a clear upward trend in air temperatures since the station began recording data. Average summer temperatures have risen by four degrees Fahrenheit and average annual temperatures have risen by one degree Fahrenheit.







Higher Variability in Rainfall

Annual rainfall within the Big Dutchman Creek shifts in precipitation patterns demand adaptive Watershed was determined by averaging the data strategies and sustainable management to mitigate their impacts. from the three closest NOAA monitoring stations. Data from these three stations goes back to The increasing variability in rainfall patterns 1941. Since then, the variability between dry and coupled with rising air temperatures have led wet years has risen significantly, although the to an uptick in major storm events. Warmer air average yearly rainfall has remained about the holds more moisture, which can lead to more same. This means that the extremities of weather intense rainfall during storms, while added heat patterns are intensifying, droughts are becoming energy in the atmosphere and ocean contributes more severe, and rainy seasons are seeing more to the strength and frequency of such events. excessive downpours. This heightened variability These storms can cause significant economic and environmental turmoil, as illustrated in has profound impacts on human, animal, and Figure 6.4. Economically, the damage from these plant life. For humans, more severe droughts can storms can be astronomical as they ravage lead to water shortages, reduced agricultural critical infrastructure, halt industry operations, yields, and economic challenges. Intense rainy decimate agriculture, and demand enormous seasons can result in flooding, property damage, resources for recovery and rebuilding efforts. and increased risks of waterborne illness. Animals The natural environment is also significantly may struggle with these rapid changes; droughts impacted as major storms can cause habitat destruction, soil erosion, water contamination, reduce the available water while flooding can and loss of biodiversity. The increased intensity destroy habitat. Similarly, plant life can be and frequency of these events is evident in stressed with such erratic rainfall patterns. Figure 6.5 and 6.6 Prolonged dry spells can reduce plant growth, while excessive rain might inundate plants. Such



Figure 6.4 Storm damage near Rock Hill, SC (The Augusta Chronicle)

20.00





Figure 6.5 Increasing variability in rainfall in the watershed



Methods for Improving Climate Resiliency

Resilient Designs

Resilient design in infrastructure and architecture ensures that communities are better equipped to withstand and rapidly recover from climate-induced disruptions. This includes the construction of buildings and bridges that can endure extreme weather, the elevation of structures in flood-prone areas, and the incorporation of renewable energy systems that remain operational during power outages. Resilient urban planning also entails designing green spaces that reduce heat island effects as shown in Figure 6.7. Green spaces also reduce the burden on drainage systems by managing stormwater. By prioritizing flexibility, redundancy, and adaptability, resilient design enables communities to maintain critical functions during severe weather events and adapt to the evolving patterns of a changing climate.

Rural regions have larger evapotranspiration rates and open spaces reflect solar energy out into space

Cities have less evapotranspiration and buildings trap solar radiation




Figure 6.7 Urban heat island effect (Public Health Notes)

Green Stormwater Infrastructure (GSI)

GSI can play a pivotal role in bolstering climate change resiliency. GSI offers innovative solutions to address the increasing rainfall that is associated with climate change. Practices aimed at mimicking pre-development hydrology, like rain gardens, green roofs, permeable pavement, and bioswales, are exemplified by a green roof shown in Figure 6.8. These practices can capture, filter, and slowly release stormwater, thus reducing the strain on traditional stormwater infrastructure. By promoting stormwater infiltration, these practices can recharge ground water supplies, decrease surface runoff, and prevent soil erosion. Additionally, GSI helps in reducing the urban heat island effect (a phenomenon where urban areas experience significantly warmer temperatures than the rural surroundings). This can be particularly valuable in moderating the elevated temperatures associated with climate change.



Figure 6.8 A green roof on the rooftop terrace at the SkyGarden Apartment in Charleston, SC (The Post and Courier)

Ecosystem Protection & Restoration

Ecosystem protection and restoration projects, like the one shown in Figure 6.9, bolster climate change resiliency by maintaining and enhancing the natural services ecosystems provide. Healthy wetlands, forests, and other natural areas act as buffers against extreme weather events by absorbing excess rainwater. These ecosystems reduce flooding, stabilize stream banks, and provide barriers to storm surges. They also sequester carbon, helping to mitigate the longterm impacts of climate change. By investing in ecosystem protection and restoration, communities can create a natural defense against the immediate impacts of climate change while contributing to carbon reduction efforts, thereby securing a more resilient future.





Figure 6.9 Stream restoration in Falls Park, SC (Greenville News)

Sustainable Agriculture & Forestry Practices

Sustainable agriculture and forestry practices significantly enhance resilience to climate change by promoting land use that supports both food security and ecosystem health. Agroforestry, conservation tillage, and diversified cropping systems are techniques that enhance soil health, bolster water retention, and diminish vulnerability to droughts and floods. Figure 6.10 illustrates the benefits of agroforestry in this context. These practices also contribute to carbon sequestration, with well-managed farms and forests acting as carbon sinks. By fostering landscapes that are more resistant to pests, diseases, and extreme weather, sustainable practices ensure that communities remain productive in the face of climate variability.

Resilient Regulations + Policies

Resilient regulations and policies form the backbone of community efforts to adapt to climate change, establishing the standards and guidelines that shape sustainable development. By updating building codes to account for increased frequency of extreme weather events, governments can ensure that infrastructure is built to higher safety standards. Zoning laws that prevent construction in high-risk areas such as floodplains reduce vulnerability to natural disasters. Furthermore, regulations that promote the preservation and restoration of natural buffers like wetlands and forests can provide critical ecosystem services. Collectively, these forwardlooking regulations and policies lay a strong foundation for community resilience.





Figure 6.10 Benefits of agroforestry (Environmental and Energy Study Institute 2023)

DRAFT CLIMATE CHANGE CONSIDERATIONS 83



Environmental Justice (EJ)

Watershed Demographics

The socio-economic indicators within the Big Dutchman Creek Watershed reflect a community that is more economically prosperous than South Carolina as a whole. Figure 7.1 shows that the watershed's population boasts a median household income of \$69,143, a figure that surpasses South Carolina's overall median household income by a notable 17%. Furthermore, the poverty rate within the watershed stands at 9.3%, a rate that is 5.3% lower than the state's average.




Figure 7.1 Income of watershed residents compared with South Carolina residents

Figure 7.2 illustrates that the racial demographics also differ between the Big Dutchman Creek and the overall demographics of South Carolina. The Big Dutchman Creek Watershed's white population is 5.8% greater than in the rest of the state. Consequently, other racial groups are less represented within the watershed.




Figure 7.2 Demographics of watershed residents compared with South Carolina residents

Environmental Justice Considerations

Environmental Justice (EJ) plays a critical role in planning efforts as it ensures equitable access to natural resources and protection from environmental hazards for all communities, especially those that have been historically marginalized. By integrating EJ principles, the disproportionate impact of pollution and waterrelated issues on marginalized communities may be addressed, which fosters fairness in the distribution of environmental benefits and burdens. Involving marginalized communities in the planning process brings diverse perspectives and cultural lenses to the table and promotes more effective and culturally sensitive management strategies. This inclusive approach helps to create a sustainable and comprehensive Watershed Plan that is equitable to all community members.



Figure 7.3 Rock Hill, SC Christmas event (Southern Living, 2023)

Engaging with Leaders

Local community leaders should be engaged early and often when pursuing EJ. These leaders often have a deep understanding of the community's dynamics and can provide valuable insights into the most effective methods of communication. They serve as bridges between the community and decision-makers, ensuring that the concerns and needs of different groups are brought to the forefront. Public input sessions should recognize and respect the contributions, heritage, and culture of all community members. This fosters a sense of respect and belonging but also ensures that water quality initiatives are responsive to the unique dynamics of each community. By embracing this approach, EJ becomes not just a policy initiative but a practice that genuinely resonates with and empowers the diverse voices it aims to represent.

Choosing the Public Forums

Deciding on the format for public input is also important. Options may include online platforms, town hall meetings, stakeholder groups, or other interactive forums. These sessions should be accessible to everyone, considering different schedules, locations, and preferences. By offering various formats, the likelihood of broad participation is increased, enabling voices from all corners of the community to be heard. Advertising the public input sessions through diverse channels also supports EJ. Using a variety of approaches that may include radio, print media, and social media ensures that the information reaches a wide audience. Each of these approaches have a different reach and impact, making it possible to engage with a broader spectrum of the community. Communication during these sessions should be inclusive and accessible. Offering options in non-English languages like Spanish and providing American Sign Language (ASL) if needed boosts inclusivity. Additionally, using non-technical language helps to demystify projects and make the information understandable and relatable to all community members.

Distributing Benefits & Burdens

For new projects, the focus should be on creating a balance where the benefits are shared equitably across the community. This includes access to clean air and water, recreational spaces, and other environmental goods. Burdens, such as pollution or resource depletion, should not be disproportionately placed on certain groups, particularly those who are economically disadvantaged or belong to minority communities. Equitable distribution requires a nuanced understanding of the community's demographic and socio-economic landscape, ensuring that the outcomes of any environmental project do not exacerbate existing inequalities.



Figure 7.4 Clean Up Aiken, SC Volunteers keep their community clean (Clean Up Aiken)



Figure 7.5 Clean Up Aiken, SC Volunteers keep their community clean (Clean Up Aiken)



Figure 7.6 Environmental Justice Guiding Principles (DHEC, 2024)

Removing Barriers

Removing barriers to existing benefits is another critical aspect of ensuring equitable access. These barriers can be economic, such as fees that limit access to certain amenities or services. For example, imposing a fee to enter a public park can exclude lower-income individuals and families, thus denying them the benefits of the space. Physical barriers, like fences or other structures that restrict access to environmental amenities, can also be obstacles. These barriers not only physically exclude people but can also symbolize social and economic divides, reinforcing feelings of exclusion and inequality.

Institutional barriers are often more challenging to identify and dismantle. These include policies and practices that prevent meaningful engagement of all community members in environmental decision-making. Institutional barriers could manifest as complex bureaucratic processes, lack of transparency, or a decision-making framework that does not consider the voices of marginalized groups. Overcoming these barriers requires a systemic change in how institutions operate and engage with communities.

In conclusion, EJ's focus on equitable access requires a multi-dimensional approach that addresses various barriers and ensures fair distribution of environmental benefits and burdens. It demands a commitment to understanding and dismantling the structures that perpetuate inequality, ensuring that environmental policies and projects are inclusive and equitable for all community members.




Figure 7.7 Keep American Clean Presidents Circle recognition (Rock Hill Clean and Green)



Figure 7.8 Northwestern High School Litter Clean Up Day (Rock Hill Clean and Green)



Figure 7.9 Cherrry Park Rock Hill (Flckr).



Financial & Technical Assistance This section addresses EPA's Element D – estimate amounts of technical and financial assistance and the relevant authorities to implement the plan.

Cost Estimate for Watershed Plan

The yearly cost of implementing the management measures is estimated in Figure 8.1. The total cost for all five years is approximately \$12.6 million; however, of that cost \$10.1 million is for the <u>City of Rock Hill's</u> Wastewater Capital Improvement Plan (CIP). The remainder of the Watershed Plan implementation will

cost \$2.5 million.	Cost Per unit			20	024-2027	2	2028-2031	20	32-2035	2	036-2039		ual cost from 40 onwards
				#	Cost	#	Cost	#	Cost	#	Cost	#	Cost
1. Reduce Bacteria & Nutrients from Humans			· · ·					· · · ·		·		· · · ·	
Repair & replace failing septic systems	\$1,775	per system fixed				15	\$26,625	15	\$26,625	15	\$26,625	5	\$8,875
Connect failing septic systems to sanitary sewer	\$2,400	per system connected				70	\$168,000	70	\$168,000	70	\$168,000	25	\$60,000
Install rain gardens (residential)	\$4	per square foot					\$1,000		\$1,000		\$1,000	85	\$340
Install rain gardens (commercial)	\$25	per square foot					\$3,125	125	\$3,125	125	\$3,125	40	\$1,000
Implement Rock Hill's wastewater CIP	\$2,500,000	per fiscal year 2025-2028		2	\$5,000,000	1	\$2,500,00						
Remove litter from streams	\$8,065	per ton of litter removed						2	\$16,130	8	\$64,520	1	\$8,065
Remove litter from streets	\$1,000	per ton of litter removed						5	\$5,000	20	\$20,000	5	\$5,000
Sweep streets	\$94	per mile of street swept						120	\$11,280		\$45,120	120	\$11,280
Convert dry detention ponds to wetlands	\$165,000	per conversion								2	\$330,000	1	\$165,000
2. Reduce Bacteria & Nutrients from Animals													
Implement goose egg addling	\$60	per addled nest						18	\$1,080	24	\$1,440	6	\$360
Provide pet waste stations	\$200	per pet waste station				6	\$1,200	12	\$2,400	12	\$2,400	3	\$600
Increase catch basin cleaning	\$300	per basin cleaned						25	\$7,500		\$30,000	25	\$7,500
Exclude livestock from streams with fencing	\$2	per linear foot of fence				80	\$160	160	\$320		\$320	40	\$80
Provide alternative water sources on pastureland	\$37	per acre of pastureland				80	\$2,960	160	\$5,920		\$5,920	40	\$1,480
3. Reduce Hydrologic Impacts from Development													
Disconnect household downspouts	\$100	per downspout disconnected				10	\$1,000	20	\$2,000	20	\$2,000	5	\$500
Provide flood attenuation & storage	\$70,000	per acre of impervious area treated										2	\$140,000
Restore and enhance stream buffers	\$850	per linear foot of buffer re- stored									\$340,000	100	\$85,000
Restore eroding streams	\$850	per linear foot of stream re- stored									\$340,000	100	\$85,000
Restore floodplains	\$15,000	per acre of floodplain restored								8	\$120,000	1	\$15,000
4. Increase Education & Outreach													
Provide septic & sanitary system education	\$10,000	per year		1	\$10,000	1	\$10,000	1	\$10,000	1	\$10,000		\$2,500
Provide pet waste education & signage	\$10,000	per year		1	\$10,000	1	\$10,000	1	\$10,000	1	\$10,000		\$2,500
Provide lawn care education	\$2	per household or business					\$1,600		\$1,600		\$1,600		\$400
Provide educational signage	\$200	per installed sign		45	\$9,000								
Increase coverage of water quality in the media	\$10,000	per year		2	\$20,000	4	\$40,000	4	\$40,000	4	\$40,000	1	\$10,000
Expand existing education program	\$5,000	per year		2	\$10,000	4	\$20,000	4	\$20,000	4	\$20,000	1	\$5,000


Figure 8.1 Estimated costs for Watershed Plan implementation

Funding Sources & Partners

Successfully implementing this Watershed Plan will require funding and partners who can assist by providing volunteers and technical assistance. Specific expertise may be needed for management measure design, siting, and construction and implementing education and outreach programs. Figure 8.2 below provides information about programs and organizations that can help provide the needed resources.

		Fundi	ng Soi	urces		Vo	lunteer Assista	ance	Financial & Technical Assistance							
	Section 319	SC State Revolving Fund	USDA	FEMA BRIC	Rock Hill SW Fee	Rock Hill Clean & Green	Catawba Riverkeeper	Keep York Beautiful	DHEC Watersheds Program	York Co Cooperative Extension	York Co Soil & Water					
1. Reduce Bacteria & Nutrients from Hum	ans															
Repair & replace failing septic systems									•							
Connect failing septic systems to sanitary sewer									•							
Install rain gardens (residential)						•			•							
Install rain gardens (commercial)		•			•	•			•							
Implement Rock Hill's wastewater CIP																
Remove litter from streams					•	•	•	•								
Remove litter from streets						•	•	•								
Sweep streets					•											
Convert dry detention ponds to wetlands	•	1		1					•	•						
2. Reduce Bacteria & Nutrients from Anin	nals															
Implement goose egg addling										•						
Provide pet waste stations									•							
Increase catch basin cleaning					•											
Exclude livestock from streams with fencing									•		•					
Provide alternative water sources on pastureland									•		•					
3. Reduce Hydrologic Impacts from Devel	opment															
Disconnect household downspouts	•						•	•	•	•						
Provide flood attenuation & storage	•			•	•				•							
Restore and enhance stream buffers									•	•	•					
Restore eroding streams	•			•	•				•	•						
Restore floodplains					•				•	•						
4. Increase Education & Outreach																
Provide septic & sanitary system education	•					•	•	•	•	•						
Provide pet waste education & signage					•	•	•	•	•	•						
Provide lawn care education	•				•	•	•	•	•	•						
Provide educational signage					•				•							
Increase coverage of water quality in the media					•	•	•	•								
Expand existing education program						•		•			•					

Figure 8.2 Sources of support for implementing the Watershed Plan



Education & Outreach

This section addresses EPA's Element E – develop an information/education component.

Overview

Engaging the community through education and outreach fosters awareness and understanding of watershed issues among the people who live, work, and play in the Big Dutchman Creek Watershed. Citizens who are well-informed about the impacts of their actions on the watershed are more likely to participate in conservation efforts and adopt environmentally responsible behaviors. Effective public education can also build community support for the Watershed Plan, ensuring sustained commitment and involvement from local stakeholders. Objective 4 of this Watershed Plan is to increase education and outreach by:

- Providing education for septic + sanitary systems;
- Providing pet waste education + signage;
- Providing lawn care education;
- Providing educational signage;
- Increasing coverage of water quality in the media; and
- Expanding existing engagement programs.

"The trash problem in York County has gotten significantly worse in the decades I've lived here... How do we stop littering?"

Public Feedback

"Increase the communication for concerns like this. Too many people don't even know what/ how/why anything is a problem."

"Local government can help drive the conversation around water quality and bring groups ' together to find viable solutions."


"When I was a kid you could look into

creeks & see lots of creatures swimming around. I looked into Little Dutchman Creek recently & saw no life."

Current Public Perceptions

Public input was collected through ArcGIS's web-based Survey123 platform. The survey was promoted via multiple channels to ensure broad community engagement. The local radio station WRHI advertised the survey and it was published on the official City of Rock Hill website. The survey garnered a total of 107 responses.

The survey was divided into two distinct versions based on the respondent's selfreported familiarity with environmental issues. This approach ensured each respondent was presented with guestions aligned to their familiarity with watershed issues.



A total of 19 respondent classified themselves as highly familiar with environmental issues and were directed to a more specialized version of the survey. This version incorporated in-depth questions regarding water quality and utilized industry-specific terminology.

The remaining respondents received a more generalized questionnaire, specifically designed to be comprehensible to a broad audience. A total of 88 respondents participated in this version of the survey.

Ten Methods to Make it Fun and Creative

Many issues are competing for the attention of the public and it can be challenging to encourage the community to prioritize watershed protection. Ensuring that education and outreach activities are fun and creative will draw more attention from the public than a serious or even a negative message. Here are a few big picture tips to engage the public in the Big Dutchman Creek Watershed:

- 1. Engage audiences by offering interactive content like guizzes, polls, and contests. This approach captures attention and encourages participation, makes them feel connected to the watershed. Interactive content can be shared easily, increasing your brand's reach.
- 2. Some of these topics, particularly pet waste management, can easily be made humorous. People are much more likely to remember the message when you have made them laugh.
- 3. Use social media to cater to the ways in which younger generations receive information.
- 4. Set up tables where people are already gathered, including community events such as Catawba Fest, ChristmasVille, the Strawberry Festival and the Come-See-Me Festival, can spread the message much further than trying to hold a separate event solely focused on watershed issues.
- 5. Provide educational signage at relevant locations such as parks, stormwater BMPs, and in pet stores (for pet waste management) so people see the message at the moment when it is pertinent.
- 6. Engage local radio shows, like WRHI, to provide updates on the implementation of the Watershed Plan, ensuring the community stays informed and engaged. Work with local news stations such as WBTV, WCNC, or WSOC to showcase more significant watershed achievements and initiatives.
- 7. Continue to foster partnerships and create new ones to help spread the message.
- 8. Create an integrated campaign that uses a variety of media and approaches to be more effective. People generally need to hear a message multiple times from different sources before they will act.
- 9. Work with the Art Council of York County to create programs, exhibits, and events that promote watershed awareness and health.
- 10. Be willing to think outside the box on how to approach watershed education.

Outreach & Education Management Measures

State and local governments have already developed a wide variety of effective and entertaining outreach and education materials for the topics identified in this Watershed Plan. Before developing new materials, it is recommended to consider the resources that already exist and to borrow ideas and approaches that have already worked elsewhere.

4a. Provide Septic & Sanitary System Education

Malfunctioning septic systems and leaking sanitary pipes are a source of E. coli and nutrient pollution. Property owners with septic systems need to hear the following messages:

- -> Here's how to maintain septic systems so it can protect your home, family and the environment.

Resources SepticSmart Educational Materials How a Septic Tank System Works Be Septic Safe



Figure 9.1 EPA "Do your part, be septic smart!" poster (EPA, 2024)

 \rightarrow Here's how to recognize and respond to signs of service line or septic system malfunctions;

→ You can prevent failures and clogs by properly disposing of grease and toxic substances; and

From
EPA
DHEC
Clemson Cooperative Extension

4b. Provide Pet Waste Education & Signage

Pet waste is a source of E. coli and nutrients. Pet owners need to hear the following messages:

- Cleaning up after you pets protects water quality and keeps outdoor amenities safe for everyone;
- → This is part of your responsibility as a pet owner; and
- → It just takes a little planning and effort to pick up after your pet.



Figure 9.2 Pet waste education can be whimsical (Dog Poop Signs – A SmartSign Store)

Resources	From
Please Clean Up After Your Pet	Beaufort County, SC
Trash the Poop	Columbia, SC
Pick it Up!	Richland County, SC
Pet Waste Management	EPA
It's Your Duty to Pick up their Doody	Durham, NC
Scoop It, Bag It, Trash It!	Maryland Dept. of Environmental Protection

4c. Provide Lawn Care Education

Improper or excessive application of lawn care products is a significant source of nutrient pollution. Property owners and lawn care professionals need to hear the following

- → Applying lawn care products at the correct times, and in the correct amounts, protects water quality, keeps lawns lush, and saves money;
- When too much fertilizer is applied to lawns, it can wind up in everyone's streams and lakes and cause algal blooms; and
- → These algal blooms can be dangerous to humans and pets.

Resources	From
Grasscycling	DHEC
Water Quality and Lawn Care	NC State Cooperative Extension
16 Steps for Eco-Friendly Lawn Care	Lawn Love
Healthy Lawn, Healthy Environment	EPA
Carolina Lawns: A Guide to Maintaining Quality Turf	NC State Cooperative Extension
	· · · · · · · · · · · · · · · · · · ·



Figure 9.3 Organic lawn care infographic (TurfGrowers)

4d. Provide Educational Signage & Increase Coverage of Water Quality in the Media

A lack of familiarity with water quality issues can lead people to inadvertently take actions that negatively impact the health of the watershed. All residents need to hear the following messages:

- → Being knowledgeable and proactive when it comes to protecting water quality is everybody's business;
- \rightarrow There are many ways that individuals can affect everyone's water quality; and
- → Stormwater BMPs require regular maintenance.



Figure 9.4 Educational signage is an easy way to provide public education about stormwater issues (McAdams)

Resources	From
What Does a Swim Advisory Mean?	DHEC
<u>Carolina Clear – Rain Gardens</u>	WBTW
Stream Bank Stabilization	Upstate Forever
Creek Friendly	Wilmington, NC
See It. Report It.	Wilmington, NC



4e. Expand Existing Education Programs

Residents want to help improve the environmental conditions within the watershed but may not know how. All residents need to hear the following messages:

- \rightarrow There are many programs, initiatives, and ways to get involved with protecting water quality within the watershed; and
- \rightarrow Your contributions can make a meaningful difference.



Figure 9.5 The Adopt-a-Stream program provides education while keeping waterways clean (DHEC)

Resources	From
Adopt a Stream Program	DHEC & Clemson University
<u>Catawba Riverkeeper</u>	Catawba Riverkeeper
Rock Hill Clean & Green	City of Rock Hill
Keep York County Beautiful	York County, SC



Implementation Timeline & Milestones This section addresses EPA's Elements F and G – develop a project schedule and

describe the interim, measurable milestones.

Overview


The most important part of Watershed Planning is to implement the management measures. This process is more successful if each management measure is separated into a series of interim milestones with a schedule for each milestone, as shown in Figure 10.1a and 10.1b. The implementation timeline for this Watershed Plan puts education and outreach programs at

the beginning of the implementation process to engage citizens and stakeholders while planning for some of the on-the-ground measures is conducted. Goals and milestones will change over time as the Key Partners and others involved in implementing plan learn from their efforts and make refinements. This implementation timeline will likely be modified over time.

Management Measures	Milestones	'24	'25	'26	'27	'28	'29	'30	'31	'32	'33	'34	'35	'36	'37	'38	'39	'40+
	Determine location/content for signage																	
	Design signage		•															
Provide educational signage	Identify funding for signs																	
	Install signs																	
	Ongoing maintenance of signs				>													
	Determine which outlets to use		•															
	Create/update content																	
Increase coverage of water quality in the media	Identify funding & free coverage opportunities																	
	Create/update schedule for media coverage																	
	Execute media coverage plan			>														
Expand existing engagement pro-	Determine needs of existing programs		•										•					
grams	Create & executes plan to address needs			→														
Provide education for septic & sani-	Contact homeowners via mail & media								•									
tary systems	Provide workshops & educational materials																	
	Identify funding sources/cost-share																	
Repair/replace failing septic systems	Visit homes & determine solutions needed																	
or connect failing septic systems to sanitary sewer	Implement needed solutions					>												
	Ensure ongoing maintenance of solution						>											

Management Measures	Milestones	'24	25	26 '26	27	28 '	29	'30	'31	'32	'33	'34	'35	'36	'37	'38	'39	'40+
Provide alternative water sources on	Contact pasture owners																	
pastureland	Provide funding & technical assistance							→										
Exclude livestock from streams with	Contact pasture owners																	
fencing	Provide funding & technical assistance							→										
	Design or select pet education materials																	
Provide pet waste education & signage	Provide education via vets & media			→														
	Install signs in parks & other targeted areas																	
	Target locations to install pet waste stations																	
Provide pet waste stations	Identify funding																	
	Install & maintain stations						→											
	Identify funding sources/cost-share																	
Disconnect household downspouts	Contact homeowners via mail & media																	
	Provide funding & technical assistance						→											
	Design or select lawn education materials																	
Provide lawn care education	Distribute materials to property owners												•					
	Contact owners of ponds with geese														•			
Implement goose egg addling	Identify funding														•			
	Implement addling										→							
	Convene existing outreach organizations																	
	Assess & prioritize needs																	
Remove litter from streams & streets	Create a schedule for cleanup activities																	
	Implement schedule												→					
	Assess & prioritize needs																•	
Sweep streets	Create a schedule for sweeping activities												→					
	Assess & prioritize needs																•	
Increase catch basin cleaning	Create a schedule for cleaning												→					
Restore & enhance stream buffers,	Identify priorities																	
eroding streams and impacted	Seek grant funding														•			
floodplains	Implement stream & buffer enhancements															→		
	Identify priorities														•			
Convert dry detention ponds to wetlands	Seek grant funding																	
wedanus	Implement dry detention pond conversions																→	
	Identify priorities																	
Provide flood attenuation & storage	Seek grant funding																•	
	Implement flood attenuation & storage																	→
 Time limited task 																		
	1																	

	0na	aina	Tool
7	Unu	omu	Task



Evaluation Criteria

This section addresses EPA's Element H – identify indicators to measure progress.

Overview

The recommended management measures will be implemented by numerous organizations in multiple locations. Therefore, the contributors need to track their progress and to view the efforts of others. This will enable the Key Partners to make datadriven decisions about which measures are most cost-effective and emphasize those measures in future efforts. This section provides metrics for tracking implementation and a recommendation to create a digital watershed dashboard to facilitate seamless teamwork between partners.

Digital Watershed Dashboard

A digital dashboard, like the example shown in Figure 11.1, is a powerful analysis tool that can allow Key Partners to track, analyze and report on Watershed Plan progress. This dashboard would be a repository of both locational and descriptive information for tracking the progress of Watershed Plan implementation. ArcGIS Survey123 is an excellent platform for digital dashboards because it integrates with existing GIS systems and can be customized based on the preferences of the watershed partners.

Benefits of a Digital Dashboard

Seamless Communication of Real-Time Data:

Immediately after data is entered by a Key Partner, it can be viewed by other partners and, if desired, the public.

Ability to View Data in a Map or List Format:

Watershed Plan data can be viewed on a map or in a list format based on the needs of different users. For Key Partners, this means the ability to cast either a wide or narrow net over the data, focusing on the details most pertinent to their roles and responsibilities. With interactive data visualizations, digital dashboards allow for improved decision-making process and continuous growth.

Ability to Connect Watershed Efforts with Water Quality Data:

Being able to simultaneously view the locations and timing of management measures with water quality data is the only way to draw conclusions about the effectiveness of the efforts.

Opportunity for Public Outreach

If the dashboard were made publicly available, the successes and ongoing efforts of the Watershed Plan could be showcased, which would bolster community engagement and support. This approach would inform the public and foster a sense of collective responsibility and accomplishment.




Figure 11.1 Example of digital tracking dashboard (McAdams)

Evaluation Criteria

The tracking metric for each management measure is provided in Figure 11.2 below.

C	Overall Plan Objectives
	Reduce E. coli load by 30%
	Reduce TN load by 15%
	Reduce TP load by 30%
1	. Reduce Bacteria & Nutrients from Huma
	Repair & replace failing septic systems
	Connect failing septic to sanitary sewer
	Implement Rock Hill's wastewater CIP
	Remove litter from streams
	Remove litter from streets
	Sweep streets
	Convert dry detention ponds to wetlands
2	2. Reduce Bacteria & Nutrients from Anim
	Implement goose egg addling
	Provide pet waste stations
	Increase catch basin cleaning
	Exclude livestock from streams with fencing
	Provide alternative water sources on pastureland
3	3. Reduce Hydrologic Impacts from Develo
	Disconnect household downspouts
	Provide flood attenuation & storage
	Restore and enhance stream buffers
	Restore eroding streams
	Restore floodplains
4	I. Increase Education & Outreach
	Provide septic & sanitary system education
	Provide pet waste education & signage
	Provide lawn care education
	Provide educational signage
	Increase coverage of water quality in the media


Figure 11.2 Tracking metric for measurement measures

ans

als

opr

Tracking Metric
Concentration of E. coli in water samples
Concentration of TN in water samples
Concentration of TP in water samples
of repaired/replaced septic systems
of homes converted to sanitary sewer
of sanitary sewer repairs
Tons of litter removed from streams
Tons of litter removed from streets/ROW
Miles of streets swept
of wetland conversions
of addled goose nests
of installed pet waste stations
of catch basins cleaned
Feet of fencing installed along pastureland
Acres of pasture served by alternative water sources
nent
of household downspout disconnections
of flood attenuation BMPs installed
Miles of restored/enhanced stream buffers
Miles of restored stream banks
Acres of restored floodplains
of citizens educated about septic & sanitary systems
of citizens educated about pet waste
of citizens educated about lawn care
of educational signs installed
of water quality news stories





Overview

Without consistent and systematic monitoring, it is impossible to determine if the implemented management measures are effectively enhancing water quality in the watershed. By conducting thorough water quality evaluations, the evaluation criteria can be compared against real world

conditions. This ensures that water quality improvements are on the right track and provides valuable insights for continuous improvement and adaptation of the management strategies.




Figure 12.1 Existing and proposed sampling points in watershed map

Sampling Points

Water quality monitoring is currently limited to a single sampling point within the watershed. This point is situated near where the Big Dutchman Creek flows into the Catawba River and offers a valuable overview of the entire watershed's health. While this single snapshot is informative, it lacks the nuances necessary to accurately assess the effectiveness of newly implemented management measures across the watershed. To address this limitation, this plan proposes establishing three additional monitoring points.



Access: At the bridge on W Oak Drive

Reason to Sample: The sampling results from this location will help assess if additional management measures are needed at the pastureland in the northwestern portion of the watershed.



Access: At the bridge on Twin Lakes Road


Reason to Sample: The sampling results from this location will help assess if additional management measures are needed at the airport.



Figure 12.2 Existing and proposed sampling points in watershed summary

The proposed points are labeled 1, 2, and 3 in Figure 12.1. These new locations have been chosen to provide a more comprehensive understanding of water quality issues throughout

the watershed. The reasons for selecting these specific points, along with their locations and access methods, are detailed in Figure 12.2 below.



Access: From footpath at the end of Quiet Creek Dr (may need to obtain permission).

Reason to Sample: The sampling results from this location will help assess the impact of the denser development in the southeastern portion of the watershed.



Access: At the bridge on Mt Gallant Road

Reason to Sample: This is DHEC's existing sampling location, and it shows the overall health of the watershed.




Sampling Parameters

When? Samples from each monitoring site should be collected monthly. This is the same monitoring schedual implemented by DHEC and required by the Adopt-a-Stream program.

What? To monitor the success of this Watershed Plan, sampling results must include E. coli, Total Nitrogen (TN), and Total Phosphorus (TP). Including pH, Dissolved Oxygen (DO), and turbidity is recommended because these pollutants are often associated with development and agricultural activities. Including pH, DO and turbidity would also allow for a complete picture of whether this watershed meets DHEC's water quality standards. In addition, expanding the list of parameters can also allow for early detection. Most of the effort in water quality monitoring is collecting the samples; testing for these extra parameters requires only minimal additional costs.

How? For those eager to play an active role in enhancing the water quality of the Big Dutchman Creek Watershed, participating in the <u>Adopt-</u> <u>a-Stream</u> program is an excellent opportunity. This program empowers community members by providing them with the necessary tools and training to collect valid water quality samples. By engaging in this initiative, participants can contribute to the sucess of this Watershed Plan.



Report References
Alabama Cooperative Extension System. (2022, February 1). <u>Coliform bacteria in well water - Alabama</u> <u>Cooperative Extension System.</u>
American Planning Association. (2023). <u>Land-Based Classification Standards Activity Dimension with</u> <u>Descriptions.</u>
American Water Resources Association. (2012, June). Is Urban Stream Restoration Worth It?
Art Council of York County. (2023). <u>Home Page</u> .
Axios. (2023, August 31). More than 62,000 pounds of trash removed from lowa rivers.
Bow Wow Waste. (2024). <i>Dog Waste Stations.</i>
Catawba Riverkeeper. (2023). About Catawba Riverkeeper. Mission, History, & Vision.
Chestnut, D., & Rabon, B. (2020). <i>Development and Adoption of the Escherichia coli Freshwater Water Quality Standard</i> . South Carolina Bureau of Water.
City of Durham. (2023). <i>I<u>t's your duty to pick up their doody.</u></i>
City of Kirkland. (2020). Pet Waste Bacteria Monitoring, Outreach and Education.
City of Rock Hill. (2022) <u>Zoning Ordinance.</u>
City of Rock Hill. (2022, June 28). 2021 Water Quality Consumer Confidence Report.
City of Rock Hill. (2023). <u>Bike Rock Hill.</u>
City of Rock Hill. (2023). <u>Capital Improvement Plan 2023-2028.</u>
City of Rock Hill. (2023). <u>Rock Hill Clean & Green.</u>
City of Rock Hill. (2023). <u>Stormwater Fees.</u>
City of Wilmington. (2023). <i>Report Stormwater Pollution.</i>
City of Wilmington. (2023). <u>Stormwater Solutions.</u>
Clary, J., Pechacek, L., Clark, S., Steets, B., & Pitt, R. (2014). <i>Pathogens in Urban Stormwater Systems</i> . Pathogens in Wet Weather Flows Technical Committee.
Clemson Cooperative Extension. (2022, May 24). <i>Be Septic Safe: Considerations for New Septic System</i> Users, Locating the System, & Basic Maintenance.
Clemson Cooperative Extension. (2023). Pet Waste & Water Quality.
Clemson Cooperative Extension. (2023). York County Extension Office.
Columbia Water. (2023). <u>Trash the Poop.</u>
Connecticut Department of Energy & Environmental Protection. (2022, March 31). <u>Problems with</u> <u>Canada Geese.</u>
Fairfax County. (2005). Popes Head Creek Watershed Management Plan.
Federal Emergency Management Agency. (2020, February 4). Debris Removal from Catch Basins.
Federal Emergency Management Agency. (2020, July 8). <i>Elood Zones.</i>
Federal Geographic Data Committee, Wetlands Subcommittee. (2013). <u>Classification of Wetlands and</u> <u>Deepwater Habitats of the United States (FGDC-STD-004-2013)</u> . U.S. Fish and Wildlife Service.
Forbes. (2023, April 20). <i>How Much Does Septic Tank Repair Cost?</i>
Gibb T., M. E. (2022, January 21). <u>Nutrients from septic systems can impact well and Surface Water.</u> Michigan State University Extension.

Report References	
Gould, Kevin. (2012, March 26). <u>Watering Sys</u> Extension.	ter
Interstate Commission on the Potomac Rive	er B
Iowa State University. (2012, February). <u>Estir</u>	nat
Klapproth, J. and Johnson, J. (2009). <u>Under</u> <u>Effects on Plant and Animal Communities</u> . E University. Publication 420-152.	
Lawn Love. (2023, November 21). <u>16 Steps f</u>	or E
Li, X et al. (2017). <i>Fate of Nitrogen in Subsur</i> Water Science Engineering.	fac
Lusk, M., Toor, G, and Obreza, T. (2019). <u>Onsit</u> University of Florida Extension.	<u>e S</u>
Minnesota Pollution Control Agency. (2022, <u>co-benefits of street sweeping.</u> Minnesota	Nov i St
Minnesota Pollution Control Agency. (2023). street sweeping program.	<u>Co</u>
Montomery County Department of Environm	nen
Museum of York County. (2023). <u>History</u> .	
National Oceanic and Atmospheric Administ	rat
National Wildlife Federation. (2023). Protection	ng
News Center. (2023, May 30). <i>Restoring Stre</i>	arr
Nick's Window Cleaning. (2017, May 12). What	t is
North Carolina Department of Environment a <u>Riparian Buffer Rules.</u>	anc
North Carolina Department of Environmenta (SNAP) Accounting Tool.	ıl Q
North Carolina State University Extension. (2 <u>Quality Turf in the Landscape.</u>	202
North Carolina State University Extension. (2	202
North Carolina Wetlands. (2019, November 2 <u>wetlands.</u>	0).
Rhea, D. (2022, August 24). <u>What is sedimer</u> Extension	nt a
Richland Countywide Stormwater Consortiu	m.
Ruiz, Nelly, et al. (2017, May). <u>Minimizing Stor</u> Oklahoma State University Extension	mv
Schueler, T. 1995. The architecture of urban 155-163.	str
South Carolina Department of Health and Er	nvir
South Carolina Department of Health and Er	nvir

References

ms for Grazing (E3097). Michigan State University

Basin. (2024). *How to Create a Rain Garden*.

ited Costs for Livestock Fencing.

anding the Science Behind Riparian Forest Buffers: cksburg, VA: Virginia Polytechnic Institute and State

Eco-Friendly Lawn Care.

ce Infiltration Systems for Treating Secondary Effluent.

Sewage Treatment and Disposal Systems: Phosphorus.

ovember 1). *Overview, water quality benefits, and other* Stormwater Manual.

ost considerations for establishing and maintaining a

ntal Protection. (2023). <u>Pet Waste</u>.

tion. (2023). <u>Global Summary of the Year (GSOY), Version</u>

and Restoring Floodplains.

<u>ms to Help the Environment.</u>

s a Downspout Disconnection and Why Do It?

d Natural Resources. (2022, September 7). Jordan Lake

Quality. (2023). <u>Stormwater Nutrient and Phosphorus</u>

21, July 2). *Carolina Lawns: A Guide to Maintaining*____

22, July 29). Water Quality and Professional Lawn Care.

What-when-where-who of NC wetlands: North Carolina

and why is it a stormwater pollutant?. Penn State

. (2023). <u>Pick it Up!</u>

water Runoff by Disconnecting Residential Downspouts .

ream buffers. Watershed Protection Techniques, 1(4),

ironmental Control. (2023). <u>SC Watershed Atlas.</u>

ronmental Control. (2023). Adopt-A-Stream Program.

Report References	
South Carolina Department of Health and Environmental Control. (2023). <u>South Carolina 303(d) List o</u> Impaired Waters & TMDLs.	<u>of</u>
South Carolina Department of Health and Environmental Control. (2023). <u>Sanitary Sewer Overflow Lis</u> DHEC Online Services.	<u>st.</u>
South Carolina Department of Health and Environmental Control. (2023). <u>Calculating Bacterial Load</u> Reductions in South Carolina for GRTS Reporting. Bureau of Water.	
South Carolina Department of Health and Environmental Control. (2012). Watershed Water Quality Assessment: Catawba River Basin. Technical Report No. 1109-12. Bureau of Water.	
South Carolina Department of Health and Environmental Control. (2022). <u>South Carolina Simplified</u> Guide to Developing Watershed-Based Plans.	
South Carolina Department of Health and Environmental Control. (2022, June 30). <u>The State of South</u> Carolina's 2020 and 2022 Integrated Report (IR).	h_
South Carolina Department of Health and Environmental Control. (2012, June 22). <u>Regulation 61-69:</u> <u>Classified Waters.</u>	
South Carolina Department of Health and Environmental Control. (2014, June 27). <u>Regulation 61-68:</u> <u>Water Classifications and Standards</u>	
South Carolina Department of Health and Environmental Control. (2023). Section 319 Grant.	
South Carolina Department of Health and Environmental Control. (2023). <u>State Revolving Fund (SRF</u>) <u>Program.</u>	2
South Carolina Department of Health and Environmental Control. (2023). <u>How a Septic Tank System</u> <u>Works.</u>	-
South Carolina Department of Health and Environmental Control. (2023). Grasscycling.	
South Carolina Department of Health and Environmental Control. (2023). Beach Monitoring.	
South Carolina Department of Natural Resources. (2023). South Carolina Hurricanes.	
South Carolina Emergency Management Division. (2023). <u>Building Resilient Infrastructure and</u> <u>Communities (BRIC).</u>	
South Carolina Legislature. (2023). <u>Title 48 – Envirionmtnal Protection and Conservation. Chapter 1.</u> Pollution Control Act.	
U.S. Census Bureau. (2020). 1970-2020 census of Population and Housing. Department of Commerc Economics and Statistics Administration	e,
U.S. Census Bureau. (2022) <u>American Community Survey.</u> American Community Survey Office	
U.S. Department of Agriculture. (1986, June). <u>Urban Hydrology for Small Watersheds – TR-55.</u> Nation Resources Conservation Service.	al
U.S. Department of Agriculture. (2000). Agricultural Resources and Environmental Indicators, Ch. 2.1.	L
U.S. Department of Agriculture. (2009, January). <u>National Engineering Handbook Chapter 7 -</u> <u>Hydrologic Soil Groups.</u> National Resources Conservation Service.	
U.S. Department of Agriculture. (2018). <u>The Use of Egg Addling in Wildlife Damage Management.</u> Wildlife Services.	
U.S. Department of Agriculture. (2023). Environmental Quality Incentives Program.	
U.S. Department of Agriculture. (2023). <i>Riparian forest buffers. Riparian Forest Buffers.</i>	
U.S. Environmental Protection Agency. (2004, September). <u>Healthy Lawn Healthy Environment: Carir</u> for Your Lawn in an Environmentally Friendly Way.	<u>ו</u> ם
U.S. Environmental Protection Agency. (2005, November) <u>National Management Measures to Control</u> Nonpoint Source Pollution from Urban Areas .	L

Rep	ort References
	S. Environmental Protection Agency. (2013). <u>A</u> <u>ajects</u> . National Nonpoint Source Monitoring
	S. Environmental Protection Agency. (2021, D <u>arking Lot and Street Sweeping</u>
	S. Environmental Protection Agency. (2021, D <u>y Detention Ponds.</u>
U.:	S. Environmental Protection Agency. (2023).
	S. Environmental Protection Agency. (2023, F <u>aste Management.</u>
U.:	S. Environmental Protection Agency. (2023, N
	S. Environmental Protection Agency. (2023, N <u>MDLs).</u>
U.:	S. Fish & Wildlife Service. (2023). National We
U.:	S. Fish and Wildlife Service. (2023). <u>Wetlands</u> .
U.:	S. Geological Survey. (2018, June 5). <u>Phosph</u>
U.:	S. Geological Survey. (2018, May 21). <u>Nitroger</u>
U.:	S. Geological Survey. (2023). <u>What are wetlar</u>
Ur <u>Ov</u>	niversity of Nebraska. (2010). <u>Using a Cost-Ef</u> <u>coControl G to Manage Nuisance Canada Ge</u> e
	niversity of North Carolina. (2015, May 26). <u>Ho</u> astewater system?
	ostate Forever Land Conservation. (2021, Jan <u>eer's Century Park.</u>
WE	3TW News 13. (2018, July 18). <u>Carolina Clear</u> -
Yo	rk County Soil & Water Conservation District.
Yo	rk County, SC. (2023). <u>Keep York County Bea</u>
Yo	rk County. (2022, February 21). <u>York County (</u>
Yo <u>ho</u>	ork Daily Record. (2019, December 9). <u>Litter co</u> In <u>prevent it.</u>

<u>Pollutant Load Estimation for Water Quality Monitoring</u> Program.

December). <u>Stormwater Best Management Practice:</u>

December). <u>Stormwater Best Management Practices –</u>

<u>Glossary.</u>

February). <u>Stormwater Best Management Practice Pet</u>

March 6). CADDIS Volume 2: Nutrients.

November 14). *Overview of Total Maximum Daily Loads*

etlands Inventory.

2.

norus and Water. Water Science School.

n and Water. Water Science School.

nds?

ffectiveness Model to Determine the Applicability of ese.

ow much does it cost to connect to a water and

nuary 28). <u>Brushy Creek stream bank strengthened in</u>

<u>– Rain Gardens.</u>

. (2023). <u>Home Page.</u>

autiful & Volunteer Programs.

Code of Ordinances Chapter 155: Zoning Code.

osts money, and guess what? You're paying for it. Here's

Photograph and Figure References
American Association of Retired Persons (2021, April 13). <u>5 Steps to Build a Serene Rain Garden.</u>
Alabama Cooperative Extension System. (2022, February 1). <u>Coliform bacteria in well water - Alabama</u> <u>Cooperative Extension System.</u>
Army Corps of Engineers. (2023). <i>Corps Lakes Photo Album</i> .
Carolina Thread Trail (2023). <u>Local Trail.</u>
City of Austin Texas. (2023). <i>Bottomland: Life on the Floodplain</i>
City of Fargo. (2023). <u>Sanitary Sewer Example</u> .
City of Naperville. (2023). <u>Stormwater Pond Maintenance</u> .
Clean Up Aiken. (2023). <u>Facebook Media</u> .
Clemson Cooperative Extension. (2023). <i>Example of incision</i> .
Dog Poop Signs. (2023). <u>Humorous Polite Dog Poop Sign: Be Responsible Or Train Your Dog To Be!</u>
Encyclopædia Britannica, inc. (2023). <u>Water Pollution</u> .
Environmental and Energy Study Institute. (2022, June 2). <u>0&A: How the Savanna Institute is Helping</u> Agroforestry Thrive in the Midwest.
Environmental Protection Agency (2014) <u>Performance of Green Infrastructure</u>
Flckr. (2019, April 17). <u>Grand Opening Celebration.</u>
Greenville News. (2017). City begins restoration project on Reedy Falls.
Highland. (2022, May 19). <i>Riparian Plant Walk at Highland.</i>
Independent Mail. (2020, January 3). <i>River and creek flooding around Clemson</i> .
Keep Your County Beautiful. (2021). <i>Facebook Photo. Facebook.</i>
Minnesota Pollution Control Agency. (2023). Keep your septic system healthy.
Museum of York County (2021). <i>Ice Age Exhibit. Facebook.</i>
North American Power Sweeping Association. (2023). Chicago Street & Lot Sweeping Partners.
North Carolina Wetlands. (2019, November 20). <u>What-when-where-who of NC wetlands: North Carolina</u> wetlands.
NYC Environmental Protection. (2021). <u>State of the Sewers.</u>
Paradise Plumbing. (2023). Broken Sewer Lateral Spot Repair in Santa Barbara.
PGG Wrightson. (2020). <u>Water – the forgotten nutrient.</u>
Public Health notes. (2018). <i>Impacts of urban heat island.</i>
Random Connections. (2023). Landsford Canal Lilies and the Catawba River
Recycle Away. (2023). 10 Gallon Barrel Dog Waste Station.
River Floodplain Restoration. (2020, September 27). <u>Nutrient Retention in Ecologically Functional</u> <u>Floodplains: A Review.</u>
Rock Hill Clean & Green. Facebook <u>Photo. Facebook.</u>
Socratic. (2016, April 24). <u>What is the phosphorus cycle?</u>
South Carolina Department of Health and Environmental Control (2024). Guiding Principles (EJ).
South Carolina Department of Health and Environmental Control (2024). Adopt-A-Stream Program.
Southern Living. (2023, November 2). <u>Rock Hill, South Carolina, Transforms Into ChristmasVille Every</u> Winter.
Star Tribune. (2021). Rochester's bid to control its goose population sparks controversy.
The Freshwater Trust. (2015). Infographic: 5 Reasons to Keep Livestock Out of Rivers.

Photograph and Figure References
The Augusta Chronicle. (2011). York County officials identify 3 killed in storm that also injured 5 others.
The Pocket. (2023). The PCA Downspout Disconnection Project.
The Post and Courier. (2020). Green roofs, walls gain momentum in South Carolina.
Three Lakes Association. (2017, January 12). Nonpoint Source Pollution.
TurfGrowers. (2023). <u>Organic Lawn Care Infographic.</u>
U.S. Department of Agriculture. (2021, March 12). <i>Climate change and the future of Southern wetlands.</i>
U.S. Environmental Protection Agency. (2023). SepticSmart Education Materials.
U.S. Environmental Protection Agency. (2024, January 10). Do Your Part Get SepticSmart Infographic.
University of Maryland (2016). <u>Upper Potomac Headwaters Conceptual Diagram.</u> Center for Environmental Science.
Vac-Tec Septic & Water LLC. (2023). <u>Septic Tank Pumping</u> . The Blue Book.
Vermont Public. (2017, December 15). <u>Nitrate Risk Near Farms: A Hydrogeologist Explains</u> .
Western Pennsylvania Conservancy. (2023). Streambank Fencing and Crossings.
York County Clean and Green. (2023). <i>Facebook Photos</i> .

Geographic Information System References
Open Data Hub for York County South Carolina. (2023). <u>Jurisdiction Boundaries [Data Set].</u> York County South Carolina.
The National Map. (2017). <u>NHDPlus High Resolution [Data Set].</u> U.S. Geological Survey.
Open Data Hub for York County South Carolina. (2023). <u>Flood Hazard Zone Areas (DFIRM 2017) [Data Set].</u> York County South Carolina.
City of Rock Hill. (2022). <u>Zoning Ordinance.</u>
York County. (2022). <u>Code of Ordinances.</u>
Digital Coast: Data Access Viewer. (2021). <u>USDA NAIP 4-Band 8 Bit Imagery: South Carolina [Raster].</u> National Oceanic and Atmospheric Administration.
National Land Cover Database. (2019). <u>NLCD 2019 Land Cover [Data Set]</u> . Multi-Resolution Land Characteristics Consortium.
Open Data Hub for York County South Carolina. (2023). Existing Land Use [Data Set]. York County South Carolina.
Open Data Hub for York County South Carolina. (2023). <u>Parcels [Data Set].</u> York County South Carolina.
SC Watershed Atlas. (n.d.). <i>Livestock Operations [Data Set].</i> South Carolina Department of Health and Environmental Control.
Web Soil Survey. (2020). <u>Soil Survey Geographic (SSURGO) Database for York County, South Carolina [Data Set].</u> U.S. Department of Agriculture, Natural Resources Conservation Service.
National Wetlands Inventory. (2023). <u>Wetlands Data Layer [Data Set]</u> . U.S. Fish and Wildlife Service.
The National Map. (2020). <u>USGS 1/3 Arc Second DEM [Raster]</u> . U.S. Geological Survey.
Open Data Hub for York County South Carolina. (2021). <u>Public Water Supply Intakes [Data Set]</u> . York County South Carolina.
City of Rock Hill. (2023). SewerOver [Data Set]. Personal Communication.
South Carolina Department of Health and Environmental Control. (2023). SSO List [Data Table].
City of Rock Hill. (2023). SampleData [Data Set]. Personal Communication.
Geographic Information Section (2023). <u>2022 Water Quality Assessments and 303(d) list [Data Set].</u> South Carolina Department of Health and Environmental Control

Open Data Hub for York County South Carolina. (2023). <u>TMDL Monitoring Stations [Data Set]</u>. York County South Carolina.

Big Dutchman Creek Watershed Plan

Spring 2024

