

South Carolina Department of Health and Environmental Control

Columbia MGP/ Congaree River Tar Site



Purpose of Meeting

- Brief History
- Update progress since the last public meeting Mar. 21, 2013
- Discuss issues with Removal Action
- Discuss cleanup alternatives
- Discuss path forward



Roles and Responsibilities

- SCE&G The Responsible Party (RP) for the Tar-Like Material (TLM) in the Congaree River
- DHEC Responsible for overseeing the actions of the RP to address the TLM
- US Army Corps of Engineers Responsible for reviewing a proposed activity by the RP to determine if a permit can be issued Under the Clean Water Act or the Rivers and Harbors Act



History

- Tar like material (TLM) in the Congaree River was reported in June 2010 by a citizen complaint
- DHEC responded by posting no swimming signs, collecting samples and looking for a source
- The source was determined to originate from a former Manufactured Gas Plant located on Huger St.




























dhec South Carolina Department of Health and Environmental Control





Risks of TLM in the River

- The primary potential risk is from direct contact with the TLM
- Undisturbed, the TLM is not dissolving into the river water and poses little risk to the water quality. This is based on water sampling results as well as the fact TLM is still present 60 to 100 years after it entered the river environment.



Evaluation of Cleanup Alternatives

- Environmental Evaluation / Cost Analysis, January 2013
- March 21, 2013 Public Meeting held on 4 alternatives. Public comment was invited.
- Goal is to find a solution that is protective of Human Health and the Environment and that is implementable.



dhec South Carolina Department of Health and Environmental Control

REMOVAL ACTION ALTERNATIVES

Congaree River Sediments Columbia, South Carolina

Alternative Description No Action - retained as a baseline for comparison with other alternatives. The TLM 1 would be left in place. Monitoring and Institutional Controls - The TLM would be left in place and access restrictions would be established by the installation of signs and a chain link fence along 2 the shoreline. Yearly monitoring of sediment conditions within and downstream of the project area in order to detect potential migration of the TLM. Sediment Capping and Institutional Controls - The TLM would be left in place and an engineered cap would be installed that would include geotextile and rip rap placed over 3 top of the TLM. Institutional controls and monitoring similar to Alternative 2 would be included. Removal of the Impacted Sediment With Off-Site Disposal - The TLM would be 4 physically removed from the river. This would include construction of a cofferdam and dewatering of the project area in order to access the TLM and sediments.




Preferred Alternative from 2013

- Alternative 4 Removal of the Impacted Sediment with Off-Site Disposal
- Construction of series of temporary dams so the TLM could be removed under dry conditions.



Design and Permitting

- October 2013, SCE&G began the design and started the permitting process with the US Army Corps of Engineers for construction of a cofferdam
- Scale of the rock-based cofferdam:
 - 19 feet high
 - 60 feet wide at the base
 - Covering a total river bed area 300 ft. x 2000 ft.





Issues with Dam Construction

- Risk of increased erosion to the shoreline on the west bank;
- Risk of flooding along the west bank;
- Risk of overtopping of the cofferdam;
- Risk of catastrophic overtopping where cofferdam material and exposed Tar material would be washed downriver;
- Concerns that the cofferdam could not be adequately removed when done



So ...

- The large-scale cofferdam approach had to be re-evaluated
- Cofferdam could not meet the Army Corps of Engineers' permit requirements
- Pursue Alternative Approach to TLM Removal



An Alternative Removal Approach

In January 2015, SCE&G proposed a smaller-scale design using large sandbags instead of rocks. Through the summer of 2015 this design was developed. This design would involve isolating a smaller riverbed area to be worked on (up to 200 ft. by 900 ft.) The bags would be moved around as areas were completed.



An Alternative Removal Approach

- Army Corps and DHEC agreed to field demonstration project which began on September 29, 2015
- On October 4, 2015 the historic flood event occurred.
- The Columbia Canal failed just upriver depositing up to 5 feet of new sediments over areas planned for TLM excavation



Pre Flood Conditions October 2013





Post Flood Conditions October 2015





Field Demonstration Project Results

- Sandbags were also found not to be adequate in restricting river flow
- Infiltrations under bags and around bags was a problem
- Limitations on height of this structure was inadequate to deal with dynamic river conditions



Conclusions of Demonstration Project

- Sandbags will not allow for excavation in the dry and is not an adequate solution
- Removal is not a viable alternative for cleanup
- SCE&G requested DHEC to consider the capping and institutional controls alternative
- DHEC requested SCE&G to determine if capping will meet the Army Corps of Engineers permitting requirements



dhec South Carolina Department of Health and Environmental Control

REMOVAL ACTION ALTERNATIVES

Congaree River Sediments Columbia, South Carolina

Alternative Description No Action - retained as a baseline for comparison with other alternatives. The TLM 1 would be left in place. Monitoring and Institutional Controls - The TLM would be left in place and access restrictions would be established by the installation of signs and a chain link fence along 2 the shoreline. Yearly monitoring of sediment conditions within and downstream of the project area in order to detect potential migration of the TLM. Sediment Capping and Institutional Controls - The TLM would be left in place and an engineered cap would be installed that would include geotextile and rip rap placed over 3 top of the TLM. Institutional controls and monitoring similar to Alternative 2 would be included. Removal of the Impacted Sediment With Off-Site Disposal - The TLM would be 4 physically removed from the river. This would include construction of a cofferdam and dewatering of the project area in order to access the TLM and sediments.



Next Steps

- Awaiting decision by the Army Corps
- DHEC will hold another public meeting to present the new preferred alternative once a decision is made with a public comment period on the alternative



Questions?

www.scdhec.gov/CongareeRiver

Lucas Berresford, DHEC Project Manager, (803) 0747898-

US Army Corps of Engineers, Columbia Field Office (803) 253-3444